

15-135-21252-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Like Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 5 Twp. 16 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Beren Corporation

Lease Name Zeller Well No. 1

Office Address 970 Fourth Financial Center, Wichita, KS 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 12 1976

Application for plugging filed March 29 1983

Application for plugging approved May 12 (Verbal) 1983

Plugging commenced May 12 1983

Plugging completed May 12 1983

Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production May 11 1983

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Richard Lacy, Leon Dikes

Producing formation Lower Pawnee, Cherokee Sed. Depth to top 4222 Bottom 4233 Total Depth of Well 4330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	472'	None
				5 1/2	4329'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Tied onto casing, pumped 1 sx hulls, 20 sx cement, 20 sx gel, 50 sx cement, 5 sx gel, 90 sx cement. Pumped 35 sx cement down casing annulus.

RECEIVED  
STATE CORPORATION COMMISSION  
06-13-1983  
JUN 13 1983

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beren Corporation

Address 970 Fourth Financial Center, Wichita, KS 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Evan Mayhew (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evan C Mayhew  
970 Fourth Financial Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 1983

My commission expires November 7, 1983

Gretchen H. Jones  
Notary Public.



D R I L L E R S L O G

#1 Zeller

15-135-21252-00-00

CASING RECORD:  
467' of used 8-5/8"  
surface casing.

TOTAL DEPTH:  
4330'

COMPANY: Beren Corporation  
CONTRACTOR: Strata Drlg. Company  
COMMENCED: October 22, 1976  
COMPLETED: November 1, 1976

DESCRIPTION: C SE SE  
Section 5-16S-21W  
Ness County, Kansas  
ELEVATION: 2349' Gr.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Rock & Shale	0	500	Ran 467' of used 8-5/8" surface casing set and cemented @ 472' with 200 sacks of 60-40 Pozmix, 100 sacks of Common Cement. Cement circ. Plug down at 10:00A.M. October 23, 1976.  Ran five Drill Stem Tests  Ran electric log.  Ran 149 jts. of new 5½" casing; set at 4329' with 100 sacks of common cement, 18% salt. Plug down at 10:00 P.M. DV Tool at 1686' with 300 sacks of 50-50 Pozmix, 6% gel. Plug down at 11:30 P.M., November 1, 1976
Shale & Sand	500	1700	
Shale	1700	2590	
Lime & Shale	2590	4125	
Lime	4125	4238	
Lime & Shale	4238	4261	
Lime	4261	4330	
<u>ROTARY DEPTH: 4330'</u>			

STATE OF KANSAS )  
                  ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this November 11, 1976.

My Commission Expires: November 30, 1979

*Joy Selves*  
Joy Selves, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

MAR 30 1983

CONSERVATION DIVISION  
Wichita, Kansas

D R I L L E R S L O G

#1 Zeller

15-135-21252-00-00

LOGGING RECORD:  
467' of used 8-5/8"  
surface casing.  
TOTAL DEPTH:  
4330'

COMPANY: Beren Corporation  
CONTRACTOR: Strata Drlg. Company  
COMMENCED: October 22, 1976  
COMPLETED: November 1, 1976

DESCRIPTION: C SE SE  
Section 5-16S-21W  
Ness County, Kansas  
ELEVATION: 2349' Gr.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Rock & Shale	0	500	Ran 467' of used 8-5/8" surface casing set and cemented @ 472' with 200 sacks of 60-40 Pozmix, 100 sacks of Common Cement. Cement circ. Plug down at 10:00A.M. October 23, 1976.
Shale & Sand	500	1700	
Shale	1700	2590	
Lime & Shale	2590	4125	
Lime	4125	4238	
Lime & Shale	4238	4261	
Lime	4261	4330	Ran five Drill Stem Tests
<u>ROTARY DEPTH:</u> 4330'			Ran electric log.
			Ran 149 jts. of new 5½" casing; set at 4329' with 100 sacks of common cement, 18% salt. Plug down at 10:00 P.M. DV Tool at 1686' with 300 sacks of 50-50 Pozmix, 6% gel. Plug down at 11:30 P.M., November 1, 1976

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)


I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY  
*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this November 11, 1976.

My Commission Expires: November 30, 1979

*Joy Selves*  
Joy Selves, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1983  
CONSERVATION DIVISION  
Wichita, Kansas