


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Ness County. Sec. 11 Twp. 16S Rge. (E) 21W(W)  
Location as "NE/CNWxSWx" or footage from lines C SW SW  
Lease Owner Pickrell Drilling Company  
Lease Name Harms-Kendall "C" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed September 22, 1967  
Application for plugging filed January 4, 1968  
Application for plugging approved January 8, 1968  
Plugging commenced January 4, 1968  
Plugging completed January 7, 1968  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production December 8, 1967  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Cherokee Depth to top 4115 Bottom 4214 Total Depth of Well 4266 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None
				5 1/2"	4261'	3323'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed and pumped in 25 sacks of gel and 4 sacks of hulls. Mixed and pumped in 120 sacks of cement from 600' to 240'. Mixed and pumped in 5 sacks of gel from 240' to 45'. Mixed and pumped in 15 sacks of cement from 45' to base of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Russ Casing Pulling Inc.  
Address Box 1082, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. W. Sebitts

(If additional description is necessary, use BACK of this sheet) 01-18-1968  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1968

My commission expires May 10, 1970 L. M. Whiting Notary Public.

ROTARY DRILLING LOG

15-135-20058-00-00

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202

LOCATION: Harms-Kendall "C" No. 1  
C SW SW Section 11-16S-21W  
Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

Rotary Drilling Commenced 9-1-67  
Rotary Drilling Completed 9-11-67

CASING RECORD: (13 fts.) 8 5/8" surface casing set at 245' and cemented with 160 sacks cement. Circ. (130 fts.) 5 1/2" casing set at 4261' and cemented with 125 sacks cement. Completed at 12:10 PM, September 11, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

980	Shale & Shells	<u>C. F. S.</u>
1245	Sand	3750'
1554	Shale & Shells	4135'
1597	Anhydrite	4145'
2150	Shale & Shells	4158'
2285	Shale & Lime Streaks	4170'
2435	Lime & Shale	4183'
2800	Lime	4200'
3660	Lime & Shale	4205'
3755	Lime	4220'
3825	Lime & Shale	4225'
4091	Lime	4255'
4145	Lime, Sand & Chert	4265'
4158	Sand & Chert	
4183	Sand	
4205	Sand, Chert & Lime	<u>Slope Tests</u>
4225	Sand & Chert	2500'
4265	Chert & Lime, RTD	3000'
		3500'
		4000'

	<u>S. L. M.</u>
Board	3807.93
Strap	3805.19
Diff.	2.84 (No Correction)

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN - 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
01-09-1968

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By *C. W. Sebitts*  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 20th day of September, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

*L. M. Whiting*  
Notary Public  
L. M. Whiting