

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
RECEIVED
MAR 20 2012

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32702
Name: Kutter Oil Inc.
Address 1: 701 E River
Address 2: _____
City: Eureka State: KS Zip: 67045 + _____
Contact Person: Tim Gulick
Phone: (620) 583-4360
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss. Depth to Top: 2768 Bottom: 2786 T.D. 2825
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-015-00250-00-01
Spot Description: _____
SE NW SW Sec. 11 Twp. 26 S. R. 7 East West
1,631 Feet from North / South Line of Section
4,359 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: Marshall Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: 9-27-2011 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 2-22-11
Plugging Completed: 2-22-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface			8 5/8	95	0
Miss			5 1/2	2825	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

50 sxs. @ 1186, Perf csg. @ 250', 100 sxs. Cement @ 250 to surface.

Plugging Contractor License #: 32701 Name: C & G Drilling Inc
Address 1: 701 E River Address 2: _____
City: Eureka State: KS Zip: 67045 + _____
Phone: (620) 583-5318
Name of Party Responsible for Plugging Fees: Kutter Oil Inc
State of Kansas County, Greenwood, ss.
Tim Gulick
(Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says that he has knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

2

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
2-22-12	4488	Marshall #2	11	265	7E	Butler
CUSTOMER <u>Rutter Oil</u>						
MAILING ADDRESS <u>701 E River St.</u>						
CITY <u>Eureka</u>		STATE <u>Ks</u>	ZIP CODE <u>67045</u>			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			<u>485</u>	<u>Alan B</u>		
			<u>667</u>	<u>Allen B</u>		
			<u>437</u>	<u>Jim</u>		

JOB TYPE P/A HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT _____
 CASING DEPTH 1190' DRILL PIPE _____ TUBING 2 3/4 1190' OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Rig up to 2 3/4 Tubing. Break Circulation with 4 1/2 bbls Fresh water. Pump 50 sks Class A Cement w/ 3% Cactz. Displace with 3 1/2 bbls Fresh water. Pullout Tubing. Wait 2 hrs. Mix 1 sack 60/40 per mix Cement w/ 4% Gel. 250' to surface inside 5 1/2 casing + Annulus. Job Complete. Rig down. Well was staying Full.

Thank you

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	695.00	695.00
5406	20	MILEAGE	4.00	80.00
11045	50 sks	Class A Cement	14.95	747.50
1102	140#	Cactz 3%	.74	103.60
APR 16 2012				
1131	100 sks	60/40 per Mix Cement	12.55	1255.00
1188B	340#	Gel 4%	KCC WICHITA .21	71.40
53025	2 hrs	80 bbl Vacuum Trucks	90.00	180.00
1123	2000 gallons	City Water	16.50	n/c
5407		700 Mileage Back Truck	n/c	350.00
(181.26) \$3443.81 5% Discount QW				
			Sub Total	3482.50
			SALES TAX	142.63
			ESTIMATED TOTAL	3625.13

Revin 3737

AUTHORIZATION Will: TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

