

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4787
Name: TDI, INC.
Address 1: 1310 BISON RD
Address 2: _____
City: HAYS State: KS Zip: 67601 + _____
Contact Person: TOM DENNING
Phone: (785) 628-2593
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-26271-00-00
Spot Description: _____
NW NE SW SE Sec. 6 Twp. 13 S. R. 20 East West
1,150 Feet from North / South Line of Section
1,920 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: ELLIS
Lease Name: BITTEL Well #: 1
Date Well Completed: 4/19/12
The plugging proposal was approved on: 4/18/12 (Date)
by: ED SHUMAKER (KCC District Agent's Name)
Plugging Commenced: 4/19/12
Plugging Completed: 4/19/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8 5/8	212	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 245 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal, 1st plug @ 3812' with 25 sacks, 2nd plug @ 1525' with 25 sacks, 3rd plug @ 740' with 100 sacks, 4th plug @ 260' with 40 sacks, 5th plug @ 40' to surface with 10 sacks, 30 sacks for rat hole, 15 sacks for mouse hole, by Quality (Ticket #5496), job was completed @ 4:30 pm on 4/19/2012.

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING, INC
Address 1: 8 NORTH MAIN Address 2: PO BOX 276
City: ELLINWOOD State: KANSAS Zip: 67526 + _____
Phone: (620) 564-3800
Name of Party Responsible for Plugging Fees: TDI, INC.
State of KANSAS County, ELLIS, ss.
JILL WAHLMEIER Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

RECEIVED *AR*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

APR 25 2012

KCC WICHITA

**SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS**

Lease: Bittel #1

Plugging received from KCC representative:

Name: Ed Shumaker Date 4-18-12 Time 4:55 pm.

1st plug @ 3812 ft. 25 sx. Stands: 61

2nd plug @ 1525 ft. 25 sx. Stands: 25

3rd plug @ 740 ft. 100 sx. Stands: 12 1/2

4th plug @ 260 ft. 40 sx. Stands: 4 1/2

5th plug @ 40 ft. 10 sx. Stands: Kelly

Mousehole 15 sx.

Rahole 30 sx.

Total Cement used: 245 sx.

Type of cement 60/40 poz 4% gel 1/4" Flo Seal

Plug down @ 4:30 pm. 4-19-12

Call KCC When Completed:

Name: Rich Williams Date 4-20-12 Time 8:50 A.M.

RECEIVED
APR 25 2012
KCC WICHITA