

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32864  
Name: XTO Energy, Inc.  
Address 1: 210 Park Avenue; Suite 2350  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73102 + \_\_\_\_\_  
Contact Person: Karen Byers  
Phone: (405) 319-3212  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Winfield Depth to Top: 2585' Bottom: 2608' T.D. 2608'  
Krider Depth to Top: 2547' Bottom: 2560' T.D. \_\_\_\_\_  
Herington Depth to Top: 2536' Bottom: 2544' T.D. \_\_\_\_\_

API No. 15 - 055-00280 . 00 . 00  
Spot Description: \_\_\_\_\_  
- C - NW Sec. 17 Twp. 22 S. R. 33  East  West  
1,320 Feet from  North /  South Line of Section  
1,320 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Finney  
Lease Name: Garden Well #: 1-17  
Date Well Completed: 6/22/54  
The plugging proposal was approved on: 4/12/12 (Date)  
by: Kenny Bernasconi (KCC District Agent's Name)  
Plugging Commenced: 4/13/12  
Plugging Completed: 4/16/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	298'	NONE
		Production	5 1/2"	2584'	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 5 1/2" 10K tbg set CIBP @ 2457' , circulate hole w/ mud & cap CIBP w/ 5 sks Class "C" cement. Pull tbg up hole @ 1984' & spot 50 sks cement up to 1502' to cover Anhydrite at 1943' . POH w/ tbg & perf squeeze holes @ 1130' . Run Pkr to 900' & set . Squeeze perfs w/ 75 sks Class "C" cement to 700 psi. Pull out of hole w/ Pkr & test casing at 400 psi. Perf squeeze holes at 356' , RU down casing & circulate to surface w/ 120 sks Class "C" cement.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.  
Address 1: P.O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: Oklahoma Zip: 73534 + 1706  
Phone: (580) 467-0258  
Name of Party Responsible for Plugging Fees: XTO Energy, Inc.  
State of Oklahoma County: Oklahoma , ss.

Karen Byers

(Print Name)

Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Karen Byers

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
APR 25 2012  
KCC WICHITA