

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
67202 TYPE OR PRINT

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-101-21803-00-00  
LEASE NAME BOSLEY Wichita, KS

WELL NUMBER 1-10

NOTICE: Fill out completely 450 Ft. from S Section Line  
and return to Cons. Div. 1765 Ft. from E Section Line  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 10 TWP. 19S RGE. 28W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY LANE  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 10/7/02

Character of Well D&A (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 10/18/02  
Plugging Completed 10/18/02

The plugging proposal was approved on 10/18/02 (date)  
by Michael Maier w/KCC Dodge City, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no  
Producing Formation none Depth to Top \_\_\_\_\_ Bottom TD 4727' Show depth and  
thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	280	8 5/8	280	0
		production	4724'	5 1/2	4267	1301'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows: set CIBP w/2sxs cmt in 5 1/2" csg @ 4250'. Shot off 5 1/2" csg @ 1343'. Pull & laydown csg. Set 1st plug @ 1300' w/80sxs cmt. 2nd plug @ 810' w/ 50 sxs cmt. 3rd plug @ 240' w/40sxs cmt. 4th plug @ 40' to surface w/10sxs cmt. Well P/A. Witnessed and approved by Michael Maier w/ KCC Dodge City, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22nd day of Oct., 2002

Notary Public - Barbara J. Dodson [Signature]  
My Commission Expires: 12/16/03 Form CP-4 Re



RECEIVED  
10-28-02  
OCT 28 2002  
KCC WICHITA

OR