


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-101-20126-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane County, Sec. 16 Twp. 19 Rge. 28 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____



Locate well correctly on above
Section Plot

SW NE SW
Lease Owner Donald C. Slawson
Lease Name Thomas G Well No. 1
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/15/77 _____ 19____
Plugging completed 9/28/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4390
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	259	none
				4 1/2"	4389	1611'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4300' and ran 3 sacks cement. Loaded hole with salt water, shot pipe at 2496', 2009', 1794', 1606', pulled 50 joints. Plugged with 2 sacks hulls, 70 sacks cement, 5 sacks gel and 1 sack hulls, 60 sacks cement.

PLUGGING COMPLETE.

10-11-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of Sept. 1977

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, K.
My Comm Exp Feb 15 1979

Margaret Melcher
Notary Public.

WELL LOG

15-107-20126-0000

OPERATOR: Donald C. Slawson
 408 120 Bldg.
 Wichita, Kansas 67202 ;

LEASE: #1 Thomas 'G'
 SW NE SW of Sec. 16-19-28W
 Lane County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.

COMMENCED: September 13, 1975

COMPLETED: September 22, 1975

CASING: 8 5/8" @ 257' w/200 sx

TOTAL DEPTH: 4390 feet

0 - 1602	Shale & Sand Streaks
1602 - 1835	Sand
1835 - 1945	Shale
1945 - 2106	Shale & Shells
2106 - 2138	Anhydrite
2138 - 4045	Lime & Shale
4045 - 4390	Lime
4390	RTD

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JAMES C. REMSBERG, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Thomas 'G'.

James C. Remsberg
 JAMES C. REMSBERG

Subscribed and sworn to before me this 7th day of October, 1975

Dolores B. Coady
 Dolores B. Coady, Notary Public

My Commission Expires:

