

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-5-117

API NUMBER 15-101-21,589-0000

LEASE NAME Methodist Church

WELL NUMBER 1

3300 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 24 TWP. 19 SRGE. 28 ~~XXXX~~ (W)

COUNTY Lane

Date Well Completed 6-8-91

Plugging Commenced 6-8-91

Plugging Completed 6-8-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market - #1000, Wichita, KS 67202

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 8, 1991 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? NO If not, Is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

6-14-91

JUN 14 1991

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	214'	None

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 50 sx. cement at 2100' thru drill pipe. Spotted 10 sx. cement at 40'
Spotted 80 sx. cement at 1300' thru drill pipe. thru drill pipe.
Spotted 50 sx. cement at 700' thru drill pipe. Spotted 15 sx. cement in rathole
Spotted 50 sx. cement at 250' thru drill pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) P. O. Box 48848
Wichita, KS 67201-8848

SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 91

Carolyn J. Tjaden
Notary Public

My Commission Expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 6/03/91 month day year App. E/2. SE NE. Sec 24.. Twp .19. S, Rg 28.. East West

OPERATOR: License # 4767
 Name: Ritchie Exploration, Inc.
 Address: 125 N. Market, Suite 1000
 City/State/Zip: Wichita, KS 167202
 Contact Person: Rocky Milford
 Phone: 316/267-4375

3300 feet from South line of Section
330 feet from East line of Section
 (Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5420
 Name: White & Ellis Drilling, Inc.

County: Lane
 Lease Name: Methodist Church Well #: 1
 Field Name: wildcat
 Is this a Prorated Field? yes no
 Target Formation(s): L/KC. & Miss
 Nearest lease or unit boundary: 330'
 Ground Surface Elevation: 2740' feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Depth to bottom of fresh water: 75'
 Depth to bottom of usable water: 1175'
 Surface Pipe by Alternate: 1 2
 Length of Surface Pipe Planned to be set: 200'
 Length of Conductor pipe required: none
 Projected Total Depth: 4700'
 Formation at Total Depth: Miss
 Water Source for Drilling Operations:

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWD Disposal Wildcat Cable
 Seismic; # of Holes

If OWD: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no
 If yes, total depth location: _____


RECEIVED
 STATE CORPORATION COMMISSION
 JUN 13 1991
 DWR Permit #: _____
 Will Cores Be Taken?: yes no
 If yes, proposed zone: _____

AFFIDAVIT

CONSERVATION DIVISION
 Wichita, Kansas
 et. seq.
 It is agreed that the following minimum requirements will be met:

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101.

SPUD DATE	<u>6-2-91</u>	INIT.	<u>RL</u>
LENGTH SURFACE PIPE	<u>200</u>		
RESERVE PIT	<u>1</u>	US - REMOVE FLUID	<u>LINED</u>
after salt seal		bbbls. when done	<u>bbbls.</u>
RATINUED AHE/			
SURFACE PIPE	<u>2 1/2</u>	SIZE HOLE	
AMMONITE T-	<u>204</u>	CONDUCTOR	
TD	<u>4660</u>	ELEVATION	
RAH PIPE			
Arbuckl.		DV TOOL	<u>SX</u> Y <u>N</u>
Plug./Conducting @		Ft. W/	<u>SX</u>
Anhydrite @	<u>2100</u>	Ft. W/	<u>50 SX</u>
1/2 Bas.	<u>1300</u>	Ft. W/	<u>80 SX</u>
1/2, 1/2	<u>700</u>	Ft. W/	<u>50 SX</u>
Bottom	<u>250</u>	Ft. W/	<u>50 SX</u>
40' Plug	<u>40</u>	Ft. W/	<u>40 SX</u>
847 HOSE CIRCUIT		Ft. W/	<u>SX</u>
	<u>15</u>	SX MOUSE HOLE W/	<u>SX</u>
		SX (Irr. Well Hauling	
		DATE <u>6-2-91</u>	
	<u>60/40 67</u>	<u>1/4 FC/100K</u>	
	<u>10:00</u>	(AM/PM) DATE <u>6-8-9</u>	
	<u>10:45</u>	(AM/PM) DATE <u>6-8-9</u>	
		<u>ALLIED</u>	



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Ritchie Exploration, Inc., 125 N. Market - Suite 1000,
Wichita, KS 67202
CONTRACTOR: White & Ellis Drilling, Inc., P. O. Box 48848,
Wichita, Kansas 67201-8848

Lease Name Methodist Church Well No. 1
Sec. 24 T. 19S R. 28W Spot App E/2 SE NE
County Lane State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 216' with 135 sx.
Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4660'
Drilling Commenced 5-31-91 Drilling Completed 6-8-91

Formation	From	To	Tops
Cellar	0	5	Anhydrite 2061
Shale & Shells	5	900	Lansing/KC 4045
Shales & Sand	900	1870	Kansas City 4245
Shale	1870	2315	Marmaton/
Shale & Lime	2315	2660	Altamont 4360
Shales	2660	2905	Ft. Scott/
Shales & Lime	2905	3610	Johnson/ 4560
Lime & Shale	3610	3860	Miss 4655
Lime	3860	4660	

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1991

CONSERVATION DIVISION
Wichita, Kansas