

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,636-000

LEASE NAME Haag

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

1470 Ft. from E Section Line

SEC. 24 TWP. 19S RGE. 28 (E) or (W)

LEASE OPERATOR Abercrombie Drilling, Inc.

COUNTY Lane

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Date Well Completed 10-23-92

Character of Well D&A

Plugging Commenced 10-24-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-24-92

The plugging proposal was approved on 10-24-92 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	292	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Circulated heavy mud in hole; 1st plug from 2050 to 1850 w/50 sx; 2nd plug from 1350 to 1030 w/80 sx; 3rd plug from 700 to 580 w/30 sx; 4th plug from 330 to 130 w/50 sx; 5th plug from 40' to surface w/10 sx; 10 sx in mousehole; 15 sx in rathole; all cement 245 sx. 60/40 pozmix w/6% gel & 1/4# floseal per sack.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton **NOV 17 1992**

(Address) 150 N. Main, #801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 92

Susan M. Williams
Notary Public

My Commission Expires: 8-15-96



FOR KCC USE:

FORM C-1 7/9

EFFECTIVE DATE: 10-18-92

State of Kansas
NOTICE OF INTENTION TO DRILL 101-21,636-6880

FORM MUST BE TYPE

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

DISTRICT # 11
SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Spot 150' West of S/2 S/2 SE Sec 24 Twp 19 S Rg 28 Eas X Was

Expected Spud Date 10 month 12 day 92 year

OPERATOR: License # 5422
Name: Abercrombie Drilling, Inc.
Address: 150 N. Main, Suite 801
City/State/Zip: Wichita, KS 67202
Contact Person: Jack L. Partridge
Phone: (316) 262-1841

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

330' feet from South North line of Section 1470' feet from East West line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side County: Lane Lease Name: Haag Well #: 1 Field Name: unknown

Is this a Prorated/Spaced Field? yes X no Target Formation(s): LKC

Nearest lease or unit boundary: 330' Ground Surface Elevation: unknown 2746 feet MS

Water well within one-quarter mile: yes X r Public water supply well within one mile: yes X r

Depth to bottom of fresh water: 80' Depth to bottom of usable water: 1300'

Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 260'

Length of Conductor pipe required: None Projected Total Depth: 4650'

Formation at Total Depth: BKC Water Source for Drilling Operations:

well X farm pond oth DNR Permit #: Will file

Will Cores Be Taken? yes X no If yes, proposed zone: N/A

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If OWWO: old well information as follows:
Operator: N/A
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location: N/A

Exp. 4/13/93

AFFIDAVIT

200' Alt. II Req.

Pusher Bill C. King
SPUD DATE 10-18-92 INIT. GB

LENGTH SURFACE PLANNED 260' of 8 7/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8" @ 292 CONDUCTOR
ANHYDRITE T- 2066 B- 2078 ELEVATION
TD 4692 FORMATION M.S.S.

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX

Anhydrite Base @ 2050 Ft. W/ 50 SX
1/2 Base Anyh. @ 1350 Ft. W/ 80 SX

1/2, 1/2 Plug @ 700 Ft. W/ 30 SX
Bottom Surface @ 330 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling
TECHNICIAN CM DATE 10-23-92

TYPE OF CEMENT 60/40 670 1/4 #
STARTING TIME 5:00 (AM/PM) DATE 10-24-92

COMPLETION TIME 11:30 (AM/PM) DATE 10-24-92
CEMENT COMPANY ACCIED