

1090133

10-17

API NUMBER 15- 135-23,614-00-00

SE NW SW, SEC. 32, T 16 S, R 21 W/E

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6668

Lease Name Thompson Well # 1-32

Operator: Theodore I. Leben & Associates  
Name & Address 105 South Broadway, Suite 640  
Wichita, KS 67202

County Ness 141.92

Well Total Depth 4367 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 17 Month: 10 Year: 19 91

Plugging proposal received from Jay Snider

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1579-1613'  
1st plug at 1620' with 50 sx cement, 2nd plug at 920' with 80 sx cement,  
3rd plug at 500' with 50 sx cement, 4th plug at 340' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 4:15 a.m. Day: 17 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement,  
2nd plug at 920' with 80 sx cement,  
3rd plug at 500' with 50 sx cement,  
4th plug at 340' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-22-1991  
OCT 22 1991

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-6-91

INV. NO. 33625

10-17

Signed [Signature] (TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 10-8-91

DISTRICT # 1  
SSAT... Yes  No

State of Kansas  
NOTICE OF INTENTION TO DRILL

15-135-23,614-00-00

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 6, 1991  
month day year

Spot SE NW SW Sec 32 Twp 16 S. Rg 21 East West

OPERATOR: License # 6668  
Name: THEODORE I. LEBEN & ASSOCIATES  
Address: 105 South Broadway - Suite 640  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Theodore I. Leben  
Phone: 316/264-2375

1650 feet from South / North line of Section  
4290 feet from East / West line of Section  
IS SECTION  REGULAR  IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Ness

CONTRACTOR: License #: 5929  
Name: DUKE DRILLING CO., INC.

Lease Name: Thompson Well #: 1-32  
Field Name: Wilcal

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OUVG ... Disposal  Wildcat ... Cable  
... Seismic: ... # of Holes ... Other

Is this a Prorated/Spaced Field? ... yes  no  
Target Formation(s): Mississippi

Nearest lease or unit boundary: 990  
Ground Surface Elevation: Unknown feet MSL

Water well within one-quarter mile: ... yes  no  
Public water supply well within one mile: ... yes  no

If OUVG: old well information as follows:

Depth to bottom of fresh water: 120'  
Depth to bottom of usable water: 350' 200'

Surface Pipe by Alternate: ... 1  2  
Length of Surface Pipe Planned to be set: 320'

Length of Conductor pipe required: N/A  
Projected Total Depth: 4300'

Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:

... well ... farm pond  other

Directional, Deviated or Horizontal wellbores? ... yes  no

DNR Permit #:  
Will Cores Be Taken? ... yes  no

If yes, true vertical depth:

STATE PROPOSITION COMMISSION  
10-22-1991

Bottom Hole Location:

Exp. 4/3/92

AFFIDAVIT

OCT 22 1991

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

CC - SURFACE DIVISION  
Wichita, Kansas

Pusher Jay  
SPUD DATE 10-10-91 INIT. DG  
LENGTH SURFACE PLANNED 320'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLE AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/2" @ 334' CONDUCTOR  
ANHYDRITE T- 1579 B-1613 ELEVATION

TD 4367 FORMATION Mississippi

RAN PIPE @ DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1620 Ft. W/ 50 SX

1/2 Base Anyh. @ 920 Ft. W/ 80 SX

1/2, 1/2 Plug @ 500 Ft. W/ 50 SX

Bottom Surface @ 340 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond  
Hauling

TECHNICIAN GMM DATE 10-16-91

TYPE OF CEMENT 60/4, 67, 14, 14

STARTING TIME 1:00 (AM/PM) DATE 10-17-91

COMPLETION TIME 4:15 (AM/PM) DATE 10-17-91

CEMENT COMPANY Alice