

To: 1 20425  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-13-92  
API NUMBER 15-135-23,647-00-00 52  
SE SE SE, SEC. 32, T. 16 S, R. 21

TECHNICIAN'S PLUGGING REPORT

Operator License # 6668  
Operator: Theodore I. Leben  
Name & Address 105 S. Broadway, Suite 640  
Wichita, KS 67202

330 feet from S section line  
330 feet from E section line  
Lease Name Irvin Well # 1-32  
County Ness 140.07  
Well Total Depth 4310 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 13 Month: 1 Year: 19 92

Plugging proposal received from Jay Snider  
(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1573-1609'  
1st plug at 1600' with 50 sx cement, 2nd plug at 900' with 80 sx cement,  
3rd plug at 360' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:25 a.m. Day: 13 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement,  
2nd plug at 900' with 80 sx cement,  
3rd plug at 360' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
01-16-1992  
**JAN 16 1992**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
Observe this plugging.

Signed Glenn R. Barlow  
(TECHNICIAN)

DATE JAN 29 1992

INV. NO. 34409

1-13 MAR 17 1992

FOR FCC USE

EFFECTIVE DATE: 1-11-92  
DISTRICT #  
STATE Yes X No

State of Kansas 15-135-23,647-00-00  
NOTICE OF INTENTION TO DRILL

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date January 6, 1992  
month day year

Spot SE SE SE Sec 32 Twp 16 S. Rg 21 East West

OPERATOR: License # 6668  
Name: THEODORE I. LEBEN  
Address: 105 South Broadway - Suite 640  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Theodore I. Leben  
Phone: 316/264-2375

330 feet from South / ~~WEST~~ line of Section  
330 feet from East / ~~WEST~~ line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5929  
Name: DUKE DRILLING CO., INC.

County: Ness  
Lease Name: IRVIN Well #: 1-32  
Field Name: Unknown

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 330

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OUVV ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
if OUVV, old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Ground Surface Elevation: 2271' feet MSL  
Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 120'  
Depth to bottom of usable water: 850'

Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 320'

Length of Conductor pipe required: N/A  
Projected Total Depth: 4300'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:  
... well ... farm pond X ... other

DNR Permit #:  
Will Cores be Taken? yes X no

If yes, proposed zones:

Directional, Deviated or Horizontal Wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

AFFIDAVIT

200' Alt. II Req.

Exp. 7/6/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101 et seq.

Pusher Sam SPUD DATE 1/6/92 INIT. DL  
LENGTH SURFACE PLANNED 320'-8 1/8"  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/8" @ 331' CONDUCTOR  
ANHYDRITE T- 159B B- 160B ELEVATION  
TD 4310 FORMATION  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
1600 Anhydrite Base @ 1600 Ft. W/ 50 SX  
1/2 Base Anyh. @ 900 Ft. W/ 80 SX  
1/2, 1/2 Plug @ 360 Ft. W/ 50 SX  
Bottom Surface @ 360 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX  
WATER WELL SX (Irr. Well Pond)  
Hauling  
TECHNICIAN GB DATE 1-8-92  
TYPE OF CEMENT 60/60 Fox 690 jcl 4 Flosser  
STARTING TIME 4:00 (AM/PM) DATE 1-13-92  
COMPLETION TIME 5:25 (AM/PM) DATE 1-13-92  
CEMENT COMPANY Atlas