

1 070874

10-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 135-23,515 -00-00

S/2 NW SE, SEC. 30, T 16 S, R 21 W/E
1650 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5472

Lease Name McCurdry Well # 1

Operator: Hoppe Oil & Gas Co., Inc.
Name & Address Landmark Square, 212 N. Market
Wichita, KS 67202

County Ness 142.51
Well Total Depth 4385 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:15 a.m. Day: 30 Month: 10 Year: 19 90

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: _____ to fill hole with heavy mud and spot cement through drill pipe Elevation 2332'
Anhydrite 1626-64'

1st plug at 1640' with 50 sx cement, 2nd plug at 870' with 80 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:20 p.m. Day: 30 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1640' with 50 sx cement,

2nd plug at 870' with 80 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

NOV 5 1990
11-05-1990

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dan Johnson
(TECHNICIAN)

DATE 11-9-90

REV. NO. 29919

10-30

EFFECTIVE DATE: 10-14-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL 15-135-23,515-00-00

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 17 90
month day year

S/2. NW. SE. Sec. 30. Twp. 16. S, Rg 21. East West

OPERATOR: License # 5472
Name: Hoppe Oil & Gas Co., Inc.
Address: Landmark Square, 212 N. Market
City/State/Zip: Wichita, KS. 67202
Contact Person: Rick A. Hoppe
Phone: (316) 265-4654

1650 feet from South line of Section
1980 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

County: Ness
Lease Name: McCurdy Well #: J
Field Name: Unknown

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 O.W.O. Disposal Wildcat Cable
 Seismic; # of Holes

Is this a Prorated Field? yes no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 660'
Ground Surface Elevation: Unknown feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 120'
Depth to bottom of usable water: 680'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 260'
Length of Conductor pipe required: None
Projected Total Depth: 4400'
Formation at Total Depth: Mississippi

If O.W.O.: old well information as follows:
Operator: N/A
Well Name:
Comp. Date: Old Total Depth

Water Source for Drilling Operations:
... well farm pond ... other
DWR Permit #: Will file
Will Cores Be Taken?: yes no
... yes, proposed zone:

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location:

250' Alt. II Req.

Exp. 4/9/91

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,

Pusher Tom Martin
SPUD DATE 10-25-90 INIT. GB

LENGTH SURFACE PLANNED 260' of 888
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 2.88 CONDUCTOR
ANHYDRITE T-1626 B-1664 ELEVATION

TD 4400 FORMATION MISS - 4400'

RAN PIPE @ DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1640 Ft. W/ 50 SX

1/2 Base Anyh. @ 870 Ft. W/ 80 SX 71w Sect.

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 330 Ft. W/ 50 SX

40' Plug @ 40-0 Ft. W/ 10 SX

RAT HOLE CIRCUM/SX MOUSE HOLE W/NA-SX

WATER WELL SX (Irr. Well Pond Hauling X)

TECHNICIAN SD DATE 10/30/90

TYPE OF CEMENT 60/40 69%

STARTING TIME 11-05 (AM/PM) DATE 1990

COMPLETION TIME (AM/PM) DATE

CEMENT COMPANY