

1 30949

5-27-88

307
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,242-00-00

NE NW NE, SEC. 29, T 16 S, R 21 W
4960 feet from S section line
1560 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Hiltabidle Well # D #1

Operator: American Energies Corporation
Name & Address: 155 North Market, Suite 710
Wichita, KS 67202

County Ness 138.94

Well Total Depth 4275 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 27 Month: 5 Year: 19 88

Plugging proposal received from Howard Cain

(company name) Beredco, Inc. (phone) 316-265-2856

work: to fill hole with heavy mud and spot cement through drill pipe Elevation 2282' KB
Anhydrite 1568-1610'

1st plug at 1590' with 50 sx cement, 2nd plug at 810' with 70 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:15 p.m. Day: 27 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,

2nd plug at 810' with 70 sx cement,

3rd plug at 270' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Steve Durrant (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN - 2 1988
06-02-1983
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-27-88

INV. NO. 21033

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Expected Spud Date: May 20, 1988
month day year
5399

API Number 15-135-23,242-00-00
NE NW NE Sec. 29 Twp. 16 S. Rg. 21 East
4960 FL from South Line of Section X West
1560 FL from East Line of Section

OPERATOR: License #
Name American Energies Corporation
Address 155 North Market, Suite 710
City, State, Zip Wichita, Kansas 67202
Contact Person Alan L. DeGood
Phone 316-263-5785

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 300 feet
County Neosho

CONTRACTOR: License # 5147
Name Beredco, Inc.
City, State Wichita, Kansas

Lease Name Hiltabidle Well # D. #1
Ground surface elevation 2268 feet MSL

Well Drilled For: Well Class: Type Equipment:
XX Oil — Storage — Infield XX Mud Rotary
— Gas — Inj X Pool Ext. — Air Rotary
— OWWO — Expl — Wildcat — Cable

Domestic well within 330 feet: — yes X no
Municipal well within one mile: — yes X no
Depth to bottom of fresh water 160
Depth to bottom of usable water 650

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set 250
Conductor pipe required N/A
Projected Total Depth 4250 feet
Formation Mississippian

I certify that 4-20-88 I will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date Signature of Operator or Agent Alan L. DeGood Title Vice-President
For KCC Use: Alan L. DeGood

Conductor Pipe Required — feet; Minimum Surface Pipe Required 200 feet per Alt. X(2)
This Authorization Expires 10-25-88 Approved By R.H. 4-25-88

EFFECTIVE DATE: 4-30-88

Spud ~~5-15-88~~
268' 8 1/8 5-21

71W

Sec. Twp. S. Rg. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

4W crush - NG

PUSHER Howard Cain
TD 4275 FORMATION MISS.
SURFACE PIPE 8 1/2" @ 266
ANHYDRITE 1568 ELEVATION 2282
STARTING TIME & DATE 8:00 AM 5-27-88
COMPLETION TIME & DATE 11:15 PM 5-27-88
1st PLUG @ 1590 FT. W/ 50 S
2nd PLUG @ 810 FT. W/ 70 S
3rd PLUG @ 270 FT. W/ 40 S
4th PLUG @ 40-0 FT. W/ 10 S
RAT HOLE CIRCULATED W/ 15 S
MOUSE HOLE CIRCULATED W/ 10 S
WATER WELL PLUGGED W/ Shaw - S
CEMENT COMPANY 6/4 690 -
TECHNICIAN S.D. ALLIOP

RECEIVED
STATE CORPORATION COMMISSION
JUN - 2 1988
06-02-1988
CONSERVATION DIVISION
Wichita, Kansas