

To: 1 18 8-16  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-135-21,222-00-00  
C SE NE, SEC. 17, T 16 S, R 24 W  
3300 feet from S section line  
660 feet from E section line

Lease Name Dubbs F Well # 1  
County Ness  
Well Total Depth 4482 145.67 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 286

TECHNICIAN'S PLUGGING REPORT  
Operator License # 31021  
Operator: Castelli Exploration Inc.  
Name & Address 9500 Westgate Dr., Ste. 101  
Oklahoma City, OK 73162

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Service License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 16 Month: 8 Year: 1995

Plugging proposal received from Dean Ives  
(company name) Castelli Exploration Inc. (phone) 405-722-5511

Work: 5 1/2" at 4481' w/100 sx cement, PBSD 4475', Perfs at 4474-67'  
1st plug sand back to 4415' and dump 5 sx cement on top of sand through bailer,  
2nd plug at 1580' with 50 sx cement, 3rd plug at 1150' with 50 sx cement,  
4th plug at 600' with 40 sx cement, 5th plug at 300' with 50 sx cement,  
6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ X \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 16 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4415' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 50 sx cement at 1580',  
3rd plug pumped 50 sx cement at 1150',  
4th plug pumped 50 sx cement at 300',  
5th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2424' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (Name) observe this plugging.

DATE 8-28-95 Signed Richard W. Lacy (TECHNICIAN)

WELL NO. 43370 8-16  
FORM CP-2/2 Rev. 01-87

RECEIVED  
STATE CORPORATION COMMISSION  
08-18-1995  
AUG 18 1995