

1060417

To:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION 100' E C SE NW SEC. 18 T 16 S, R 24 W/8X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,720 -00-00

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.

Name &amp; Address One Main Place, Suite 900

Wichita, KS 67202

3300 feet from S section line

3150 feet from E section line

Lease Name Evel Well # 1

County Ness

146.25

Well Total Depth 4500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well D&amp;A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address Box 823, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 30 Month: November Year: 19 84

Plugging proposal received from Bill Draney

(company name) Duke (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1840' with 50 sx cement

2nd plug at 1120' with 50 sx cement

3rd plug at 340' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by

Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00 pm Day: 30 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1840' with 50 sx cement, 2nd plug at 1120' with 50

sx cement, 3rd plug at 340' with 50 sx cement, 4th &amp; 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 15 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of CONSERVATION DIVISION

Wichita, Kansas

(xxx / did not) observe this plugging.

Signed

Paul A. Luthi

(TECHNICIAN)

INV. NO. 5919

FORM CP-2/3  
Rev. 01-84

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

Starting Date: November 21, 1984  
month day year

API Number is 135-22,720-00-00

OPERATOR: License # 5046  
Name Raymond Oil Company, Inc.  
Address One Main Place, Suite 900  
City/State/Zip Wichita, Kansas 67202  
Contact Person Pat Raymond  
Phone 316/267-4214


100' E. C. SE. NW. Sec 18, Twp 16, S, R. 24 x W. 36  
(location)

..3300..... 11 North from Southeast Corner of Section 18  
..3150..... 11 West from Southeast Corner of Section 18  
(Note: Locate well on Section Plat on reverse side.)

CONTRACTOR: License # 5929  
Name Duke Drilling Company, Inc.  
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line ..... 510 ..... Tex  
County ... Ness .....  
Lease Name ..... Evel ..... Well # 1 .....  
Domestic well within 330 feet :     ☐ yes     ☒ no  
Municipal well within one mile :     ☐ yes     ☒ no

<b>Well Drilled For:</b>	<b>Well Class:</b>	<b>Type Equipment:</b>
<input checked="" type="checkbox"/> Oil <input type="checkbox"/> Swd	<input type="checkbox"/> Infield	<input checked="" type="checkbox"/> Mud Rotary
<input type="checkbox"/> Gas <input type="checkbox"/> Inj	<input type="checkbox"/> Pool Ext.	<input type="checkbox"/> Air Rotary
<input type="checkbox"/> OWWO <input type="checkbox"/> Expl	<input checked="" type="checkbox"/> Wildcat	<input type="checkbox"/> Cable

Depth to Bottom of fresh water ..... 90 ..... feet  
Lowest usable water formation ..... Dakota ..... feet  
Depth to Bottom of usable water ..... 900 ..... feet  
Surface pipe by Alternate : 1 ☐ 2 ☒  
Surface pipe to be set ..... 280 ..... feet  
Conductor pipe if any required ..... None ..... feet  
Ground surface elevation ..... 2483 ..... feet MSL  
This Authorization Expires ..... 5-8-75 .....  
Approved By ..... 11-8-84  .....

If (DWWC): add rec'd info as follows:

Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth 3700 ..... feet  
Projected Formation at TD .....  
Expected Producing Formations .....

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11-7-84 Signature of Operator or Agent

Pat Raymond Title Vice President  
MHC/KOHE 11/2/01

274C/40NE 11/26/64 Form C 14B

RECEIVED  
STATE CORPORATION COMMISSION

DEC 05 1984

CONSERVATION DIVISION  
Wichita, Kansas

12-05-1984