

1 060427

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,920-00-00
4620 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123

Lease Name Anderson H Well # 1
County Ness 146.22
Well Total Depth 4499 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 232

Operator: Pickrell Drilling Company
Name & Address 110 North Market, Suite 205
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 10 Month: December Year: 19 84

Plugging proposal received from Deacon Pulley
(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" set at 4495' PBSD 4473' Open Hole
1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer
2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release
8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11:15 am Day: 10 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4495' PBSD 4473' Open Hole
1st plug sanded back to 4440' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released
8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 900 psi and shut in 100 psi.

DEC 12 1984
12-12-1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc. Recovered 2500' 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

~~I~~ did not observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

12-20-84
6078