

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22758-00-00
Spot: CSWNESW Sec/Twnshp/Rge: 33-16S-24W
2310 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: SIDEBOTTOM Well Number: 1-33
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 147.88
Surface Casing: Size 8.625 feet: 348 WITH 200 SX CMT
Production: Size 4.5 feet: 4549 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/16/2002 9:45 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LENNY UNRUH Company: RICH'S ROUSTABOUT Phone:

Proposed Plugging Method: MIX 300 # HULLS, 25 SX GEL AND 125 SX 60/40 POZ, FILL CASING, PRESSURIZE TO 500#, SHUT-IN.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/16/2002 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4464.5-4469.5'. DV TOOL AT 1258'. CMT TO SURFACE WITH 375 SX CMT. PUMP 30 SX CMT & 200# HULLS FOR BOTTOM PLUG. PUMP 15 SX GEL & 100 SX CMT. PRESSURED TO 2000# & HELD. TIED ONTO BACKSIDE & PUMPED 45 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED
OCT 24 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael J. Maier
(TECHNICIAN)
RECEIVED
OCT 21 2002
KCC Dodge City
INVOICED
DATE 10-24-02
W. NO. 200.3060702