

1 050241

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,290-00-00

SW NW SE, SEC. 10, T 16 S, R 24 WXB

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6041

Lease Name Ransom Well # 1

Operator: Petroventures, Inc.

County Ness

Name & Address 165 South Union Blvd, Suite 670

Well Total Depth 4509 146.54 feet

Lakewood, CO 80228

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hembree Well Service License Number 6907

Address Ness City, KS

Company to plug at: Hour: 7:00 am Day: 2 Month: June Year: 19 84

Plugging proposal received from Larry Benedick

(company name) Petroventures (phone) 303-455-8822

were: 4 1/2 set at 4508 Perfs 4455-4451

1st plug sand back to 4384 and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump an additional 130 sx cement.

Plugging Proposal Received by Richard M. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 am Day: 2 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4508' Perfs 4455-4451'

1st plug sanded back to 4384' and dumped 4 sx cement on top of sand, 2nd plug squeezed

well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and released

8 5/8" rubber plug and pumped an additional 130 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1984  
06-11-1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 50/50 Pozmix 4% gel 3% cc by Allied. They recovered 2481' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (check/d not) observe this plugging.

DATE 6-15-84

Signed Richard M. Lacey  
(TECHNICIAN)

INV. NO. 3038

6-2