

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,155-~~00-00~~
C. SWSW, Sec. 5, T 16 S, R 24 W/E
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5427

Lease Name Flax Well # 1

Operator: D. R. Lauck Oil Company
Name & Address: 221 S. Broadway,
Suite 400
Wichita, KS 67202

County Ness

Well Total Depth 4490 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176 Chase Kansas 67524

Company to plug at: Hour: 3:00 pm Day: 20 Month: October Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso Casing Pulling (phone) _____

were: To use 60/40 pozmix 2% gel 3% acc
1st plug off bottom with sand to 4440 + dump
4 sx of cement, Then squeeze down 8 5/8"
surface pipe w/ 35x hulls + 7sx gel + 400sx cement

Signed Richard W. Lacy + Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 Day: 20 Month: October Year: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Allied pumped the cement

Recovered 300' of 4 1/2" production casing

Maximum pump pressure is 300 psi

Shut in pressure 100 psi

Remarks: Well had been squeezed @ 1708 w/100sx +
1584 w/100sx fluid level in hole was 200 feet from
surface

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

OCT 24 1983

DATE 10-27-83

10-24-1983

INV. NO. 5931-W

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacy
(TECHNICIAN)