

1050318

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,645 - 00/Ra

NW SW SE , SEC. 26 ; T 16 S, R 22 W/E
990 ESV feet from N SE Corner of XXXX section line
2310 ESV feet from W SE Corner of XXXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Ummel "B" Well # 1

Operator: A. Scott Ritchie

County Ness

Name & Address 125 North Market, Suite 950

Well Total Depth 4425 143.81 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 24 Month: August Year: 19 84

Plugging proposal received from Terry McRae

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1960' with 50 sx cement

2nd plug at 990' with 50 sx cement

3rd plug at 300' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 am Day: 24 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1960' with 50 sx cement, 2nd plug at 990' with 50 sx

cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

(did not) observe this plugging.

INVOICED

SEP 04 1984

Signed Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

DATE 9-12-84

W.P. NO. 3641 2-24