

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,912-00-00

LEASE NAME Giess

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Lee Phillips Oil Company

SEC. 30 TWP. 16 RGE. 24 COR. (W)

ADDRESS 151 Whittier, #1400, Wichita, KS 67207-1045

COUNTY Ness

PHONE (316) 681-4470 OPERATORS LICENSE NO. 5215

Date Well Completed 11/1/95

Character of Well D&A

Plugging Commenced 11/1/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/1/95

The plugging proposal was approved on 11/1/95 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4600 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From 331'	To 0'	Size 8-5/8"	Put in 331'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged with 215 sacks 60/40 Pozmix, 6% gel, 1/4# flo seal per sack as follows: 50 sx @ 1950', 80 sx @ 1100', 50 sx @ 360', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 9:45 a.m. 11/1/95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Phillips Oil Company 11-17-1995

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 151 Whittier - #1400, Wichita, KS 6720



ALICE M. OAKS
State of Kansas
My Appt. Exp. 5-10-96

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 95

Alice M. Oaks
Notary Public Alice M. Oaks

My Commission Expires: May 10, 1996

MALLARD JV, Inc.

DRILLING CONTRACTORS

P. O. Box 1009
MCPHERSON, KS 67460

316-241-4640

Drillers Log

OPERATOR: **Lee Phillips Oil Company**
151 Whittier, Suite 1400
Wichita, KS 67207-1045

WELL: **Giess #2**

API #: 15-135-23,912-00-00

COMMENCED: **October 23, 1995**

LOCATION: **N/2 NE SE**
2310' FSL, 660' FEL
Section 30, Township 16 S, Range 24 W
Ness County, Kansas

COMPLETED: **November 1, 1995**

TOTAL DEPTH: **4600'**

ELEVATION: **2548' GL, 2553' KB**

STATUS: **Dry and Abandoned - Mississippian Formation**

SPUD: **2:55 pm 10/23/95**

SIZE HOLE DRILLED: **12-1/4" x 331'**

SURFACE CASING SIZE: **8-5/8" x 28# x 325.09' (8 jts.)**

SET AT: **331'**

CEMENT: **235 sacks 60/40 Pozmix, 2% gel, 3% cc**

SIZE HOLE DRILLED: **7-7/8" x 4600'**

PLUGGED HOLE WITH: **215 sacks 60/40 Pozmix, 6% gel, 1/4# floseal per sack as follows:**

- 50 sx @ 1950'
- 80 sx @ 1100'
- 50 sx @ 360'
- 10 sx @ 40'
- 15 sx rathole,
- 10 sx mousehole

P. D.: **9:45 am 11/1/95**

DRILL STEM TESTS: **3**

ELECTRIC LOG: **Yes**

RESERVE PIT: **38,000 ppm chlorides, 400 bbls free fluid content**

RECEIVED
KANSAS CORPORATION COMMISSION
11-17-1995
NOV 17 1995

CONSERVATION DIVISION
WICHITA, KS