


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 28 Twp. 16S Rge. (E)24 (W)
Location as "NE/CNWxSWx" or footage from lines SE NE
Lease Owner Weaver Oil Company
Lease Name Dubbs Well No. 1
Office Address 2932 Kerry Lane, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-8-1966
Application for plugging filed 10-8-1966
Application for plugging approved 10-8-1966
Plugging commenced 10-7-1966
Plugging completed 10-8-1966
Reason for abandonment of well or producing formation no oil or gas found in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Les Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280.87'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 600'. Spot 25 sacks cement. Mud back to 270', pushed plug to 270' and spot with 20 sx. cement. Mud back to 40' and capped with 10 sacks. Plugging completed at 2:15 A.M. 10-8-66.

RECEIVED
OCT 14 1966
10-14-1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct So help me God

(Signature) Wilson Rains
1425 Wichita Plaza Bldg., Wichita Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1966.

Mary J. Brown
Mary J. Brown Notary Public.

My commission expires 3-3-70

15-135-30255-00-00

ROTARY DRILLING LOG

OPERATOR: Weaver Oil Co.
#1 DUBBS
SE NE Sec. 28-16S-24W
Ness County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
COMMENCED: 9-26-66
COMPLETED: 10-8-66
REMARKS: Set 280.87' of 8-5/8" surface casing with 175 sacks HA 5 cement.

FORMATIONS

Sand	135'
Shale	282'
Shale & Shells	370'
Shale & Sand	1170'
Shale & Shells	1380'
D. Sand	1575'
Red Bed	1775'
Shale & Shells	1864'
Anhydrite	1896'
Shale & Shells & Lime	2075'
Shale & Lime	2450'
Lime w/Shale	2610'
Lime & Shale	2850'
Lime w/Shale	2925'
Shale & Lime	3000'
Lime & Shale	3160'
Lime w/Shale	3265'
Shale & Lime	3517'
Lime w/Shale	3680'
Shale w/Lime	3860'
Shale & Lime	3935'
Lime	4493'
Sand & Lime	4507'
Lime w/Chert	4570'
Rotary Total Depth (D&A)	4570'

RECEIVED
STATE CONSERVATION COMMISSION
10-14-1966
887 14 1966
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 10th day of October, 1966

My Commission Expires:
3-3-70

Mary J. Brown
Mary J. Brown, Notary Public