

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21,920-
00-00

LEASE NAME Anderson

WELL NUMBER H-1

SPOT LOCATION E/2-NE NE

SEC. 28 TWP. 16 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 12-4-84

Plugging Completed 12-10-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS Box 1303, Great Bend, Ks. 67530

PHONE # (793) 5742 OPERATORS LICENSE NO. 5123

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4499'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	232'	None
				4-1/2"	4495'	2,519.50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 4440' and 4 sacks cement. Shot casing at 3500', 3000' 2750' and 2500'. Pulled 61 joints of 4-12" casing Squeezed well with 2 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 900 psi and shut in 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc.

License No. 5000

Address Box 698, Great Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION
12-13-1984
DEC 13 1984

STATE OF Kansas COUNTY OF Barton, ss.

CONSERVATION DIVISION
Wichita, Kansas

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1984

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: _____