


15-135-20157-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 26 Twp. 16S Rge. (E) 24 (W)
Location as "NE/CNW&SW&" or footage from lines 140' W of C SE SW
Lease Owner Pickrell Drilling Company
Lease Name Dubbs "E" Well No. 2
Office Address 705 4th National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 28, 19 68
Application for plugging filed June 28, 19 68
Application for plugging approved June 28, 19 68
Plugging commenced June 28, 19 68
Plugging completed June 28, 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 900'. Set plug. Cemented with
70 sacks cement. Heavy mud to 270'. Set plug.
Cemented with 20 sacks. Heavy mud to 40'.
Set plug. Cemented with 10 sacks cement to
bottom of cellar. Plugged rat hole with 2
sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1968
CONSERVATION DIVISION
Wichita, Kansas

07-09-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS

Well, being hereby sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Building, Wichita 2, Kansas
(Address)

Sworn to before me this 1st day of July, 1968

L. M. Whiting
Notary Public.



My commission expires May 10, 1970

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 6/19/68

Rotary Drilling Completed 6/28/68

LOCATION: Dubbs "E" No. 2, 140' W of C SE SW Section 26-16S-24W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (14 jts) 8 5/8" surface casing set at 276', cemented with 160 sacks cement. Circulated. Completed 12:30 PM June 28; 1968: D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

90	Post Rock	<u>C. F. S.</u>
275	Shale, Shells, & Cement	4440
660	Shale & Shells	4520
1208	Shale & Sand	4530
1218	Blaine	
1357	Shale	
1837	Shale & Lime	
1868	Anhydrite	
2380	Shale	<u>Slope Tests</u>
4060	Shale & Lime	2000
4153	Lime	2500
4320	Lime & Shale	3000
4358	Lime	3500
4436	Lime & Shale	4000
4520	Cherokee Cong.	4500
4530	Mississippi - TD	

S. L. M.

None

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1968
CONSERVATION DIVISION
Wichita, Kansas

07-09-1968

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 9 day of July, 1968, before me the undersigned, a Notary Public, in and for the County and State of Kansas, the undersigned, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and he acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting, Notary Public

