

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-125-22290-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ness SEC. 10 TWP. 16S RGE. 24 XE/W
 Location as in quarters or footage from lines:
1650' FSL & 330' FWL of SE/4

Lease Owner Petroventures, Inc.
 Lease Name Ransom Well No. 1
 Office Address 165 S. Union Blvd., Suite 670, Lakewood, CO 80228
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed Never commercial
 Application for plugging filed 3/15/84
 Plugging commenced 6/1/84
 Plugging completed 6/3/84

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation
Non-productive in commercial quantities
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Lacey, Dodge City, KS
 Producing formation Mississippian Depth to top 4450 bottom 4550 T.D. 4509
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Mississippian</u>	<u>oil & water</u>	<u>4450</u>	<u>4550</u>	<u>8-5/8"</u>	<u>363</u>	<u>-0-</u>
				<u>4-1/2"</u>	<u>4508</u>	<u>2489</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Perforations - 4455-4482. Dump sand and spot 4 sacks cement on top of sand.
PBTD 4384'. Shoot off casing at 2481' and pull. Rig up Allied Cement and plug
as per State instructions. Pump 3 sacks of hulls, 15 sacks gel, 70 sacks cement,
50/50 POZ, 4% gel, 10 sacks gel, 1 sack hulls, 8-5/8" plug, 130 sacks cement,
50/50 POZ, 4% gel. Shut in. Plugged at 10:15 a.m. 6/2/84. State called after
job completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hembree Well Service

STATE OF Colorado COUNTY OF Jefferson, ss.
William L. Warburton (employee of owner) ~~owner or operator~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) W L Warburton
165 So. Union Blvd. Suite 670
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1984

Georgi M. Ladouceur
 Notary Public.

My Commission expires: 12-20-87

RECEIVED
 STATE CORPORATION COMMISSION
06-15-1984
 JUN 15 1984

CONSERVATION DIVISION
 Wichita, Kansas