

15-135-21477-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 10 Twp. 16S Rge. 24W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
5' West of C SE SE


Lease Owner Strata Drilling Company
Lease Name Strickler Well No. A-1
Office Address P. O. Box 355, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole

Date Well completed June 12, 1978 19
Application for plugging filed June 12, 1978 19
Application for plugging approved June 12, 1978 19
Plugging commenced June 12, 1978 19
Plugging completed June 12, 1978 19
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4475'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plug down at 4:00 a.m., June 12, 1978.

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1978
06-16-1978
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company


STATE OF KANSAS COUNTY OF BARTON, ss.
Kenneth J. Link (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1978.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.



15-135-21477-00-00

D R I L L E R S L O G

Strickler "A" #1

CASING RECORD:
7 jts. used 28#
8-5/8" surface
casing

COMPANY: Strata Drilling Company
CONTRACTOR: Strata Drilling Company
COMMENCED: June 5, 1978
COMPLETED: June 12, 1978

DESCRIPTION: 5' west
 of C SE SE
 Section 10-16S-24W
 Ness County, Kansas
ELEVATION: 2470' KB

TOTAL ROTARY
DEPTH: 4475'

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay and shale	0	295	Ran 286' used 28# 8-5/8" surface casing; set and cemented @ 291' with 190 sacks common cement, 2% gel, 3% C.C. Cement Circulated. Plug down @ 8:30 p.m., June 5, 1978.
Shale	295	400	
Shale and sand	400	1812	
Anhydrite	1812	1848	
Shale	1848	2225	Ran one drill stem test.
Lime and shale	2225	3320	
Lime	3320	3550	Ran one electric log. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plug down at 4:00 a.m., June 12, 1978.
Lime and shale	3550	4465	
Lime	4465	4475	

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

RECEIVED
STATE CONSERVATION COMMISSION
JUN 15 1978
06-16-1978
CONSERVATION DIVISION
Topeka, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Sworn to and subscribed before me this 14th day of June, 1978.

My appointment expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

