

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 100 COLORADO DERRY BUILDING
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15135 22 155
 00-00

TYPE OR PRINT
 PLEASE FILL OUT COMPLETELY
 AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Flax #1

WELL NUMBER _____

SPOT LOCATION C SW SW

SEC. 5 TWP. 16S RGE. 24W (E) OR (W)

COUNTY Ness

DATE WELL COMPLETED 1-4-82

PLUGGING COMMENCED 10-18-83

PLUGGING COMPLETED 10-20-83

LEASE OPERATOR D.R. Lauck Oil Co., Inc

ADDRESS 221 S. Broadway Suite 400 Wichita, Ks. 67202

PHONE # (316) 826-8262 OPERATORS LICENSE NO. 5077

CHARACTER OF WELL
OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL

WOULD YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, Ks.

IS ALC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION M.S.S DEPTH TO TOP _____ BOTTOM T.D. 4494'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	345'	none
				4-1/2"	4489'	342'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.
Plugged off bottom with sand to 4440' and set 4 sacks cement, shot casing @3000', 2725', 2525', 1330', pulled sub and half of landing joint when pipe parted 342' down. Pulled a total of 10 joints (342') of 4-1/2" casing. Plugged surface with 3 sacks hulls, 7 sacks gel, 225 sacks 60/40 pos, 4% gel. Plugging Complete.
400

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050

ADDRESS P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 25th DAY OF October, 1983

Irene Hoover
 NOTARY PUBLIC



RECEIVED
 STATE CORPORATION COMMISSION

OCT 28 1983
 10-28-1983
 CONSERVATION DIVISION
 Wichita, Kansas

FORM CP-4
 REVISED 06-83

COMMISSION EXPIRES: _____

15-135-22155-00-00

D. R. LAUCK OIL COMPANY, INC.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Flax #1
C SW SW Sec. 5-16S-24W
Ness County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: October 26, 1981
Completed: November 5, 1981

Drillers Log

Shale	350
Blue Clay	675
Sand	800
Shale	1854
Anhydrite	1870
Shale & Shells	1965
Shale & Salt	2425
Shale	2725
Shale & Shells	3775
Shale & Lime	3875
Lime & Shale	4110
Lime	4450
Chert	4457
Lime & Chert	4490 RTD

RECEIVED

AUG 18 1983

08-18-1983
Wichita, Kansas