


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 5 Twp. 16 Rge. 24W (XXX) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Pickrell Drilling Company
Lease Name Montgomery No. 1 Well No. 1
Office Address 705 4th Natl Bk Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 22, 19 62
Application for plugging filed September 22, 19 62
Application for plugging approved September 22, 19 62
Plugging commenced September 22, 19 62
Plugging completed September 22, 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4535 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with 25 sacks cement. Heavy mud to 40'. Set plug. Cemented with 10 sacks to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
OCT 10 1962
STATE CORPORATION COMMISSION
WICHITA, KANSAS

10-12-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th Natl Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (Conservation Division Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. W. Sebits
705 4th Natl Bk Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 62

My commission expires June 21, 1966
Maxine Blackman
Maxine Blackman
Notary Public.

15-135-00466-00-00

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth Natl Bank Bldg
Wichita 2, Kansas
LOCATION: Montgomery No. 1

Rotary Drilling Commenced 9-11-62
Rotary Drilling Completed 9-22-62

C SW NW 5-16-24
Ness County, Ks.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" Surface casing set at 260' cemented with 175 sacks quick set cement. Circulated. Completed at 2:30 P.M. 9-11-62. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface soil	
200	Shale & shells	<u>Circulated for samples</u>
262	Blue Shale	4370'
320	Shale	4450'
790	Sand	4460'
965	Shale	4470'
1235	Red Rock - Shale	4535'
1260	Blaine	
1315	Red Beds, Shale	
1575	Sand	<u>Slope Test</u>
1855	Red Bed, Shale & Shells	2000'
1860	Anhydrite	2500'
2060	Shale & Lime Shells	2900'
2225	Lime - Shale	3100'
2780	Lime	3800'
3030	Lime - Shale	
3725	Lime	<u>S.L.M.</u>
3850	Lime - Shale	3941'
3990	Lime	4284'
4250	Shale - Lime	
4470	Mississippi Top	
4535	Mississippi RTD	

RECEIVED
WINE CORPORATION COMMISSION

OCT 11 1962
CONSERVATION DIVISION

10-12-1962

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

On this 11th day of October, 19 62, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITTS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

[Signature]
Maxine Blackman Notary Public

My commission expires: June 21, 1966