

LEASE NAME Irving Trust

WELL NUMBER 1-31

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 31 TWP. 16S RGE. 22 ( ) or (X)

COUNTY Ness

Date Well Completed 4-7-95

Plugging Commenced 4-7-95

Plugging Completed 4-7-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-7-95 (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 1990'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	265'	8-5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Plugged and abandon using 60/40 Pozmix, 6% gel. Set 1st plug @ 1750' w/25 sx; 2nd plug @ 1080' w/80 sx; 3rd plug @ 600' w/40 sx; 4th plug @ 300' w/40 sx; 5th plug @ 40' w/wiper + 10 sx to surface. 15 sx in rathole, 10 sx in mousehole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address 2080 E. Kansas, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3017 N. Cypress  
Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 11 day of April, 19 95  
DEBORAH ANN PAULUS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 1-8-96  
Deborah Ann Paulus  
Notary Public  
My Commission Expires: January 8, 1996