

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23833-00-00

LEASE NAME Painter

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4290 Ft. from S Section Line

4250 Ft. from E Section Line

LEASE OPERATOR Palomino Petroleum, Inc.

SEC. 29 TWP. 16 RGE. 22 (E) or (W)

ADDRESS 4924 SE 84th Street, Newton, KS 67114-8827

COUNTY Ness

PHONE# (316) 283-0232 OPERATORS LICENSE NO. 30742

Date Well Completed 10-25-94

Character of Well Oil

Plugging Commenced 10-25-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-26-94

The plugging proposal was approved on 10-25-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Cong. Sand Depth to Top 4413 Bottom 4420 T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	248	8 5/8	248	0
	Production	0	4497	5 1/2	4497	2510

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded off perfs to TD of 4300'. Mixed 4 sacks of cement and dumped on top of sand. Shot casing off at 2510'. Spotted 1st plug at 1790 with 50 sacks; 2nd plug at 900' with 80 sacks; 3rd plug at 270' with 40 sacks; 4th plug at 40' with 10 sacks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. not required

Address 155 North Market, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF KANSAS COUNTY OF HARVEY, ss.

Klee R. Watchous, President of Palomino Petroleum, Inc. (~~Employer or Operator~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Klee R. Watchous

(Address) 4924 SE 84th Street
Newton, Kansas 67114-8827

Subscribed and sworn to before me this 10th day of November, 19 94



Kathryn L. Frerking
Notary Public

My Commission Expires: August 21, 1997