

15-135-20331-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 29 Twp. 16S Rge. (E)22 (W)
Location as "NE/CNW&SW" or footage from lines C NE SW
Lease Owner Nadel & Gussman
Lease Name Musselman Well No. 1
Office Address 1714 First Natl. Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4, 1970
Application for plugging filed (letter 4/7/70) April 4, 1970
Application for plugging approved April 4, 1970
Plugging commenced April 4, 1970
Plugging completed April 4, 1970
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4535 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	257	8-5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 660 feet. Set first plug @ 660 feet w/70 sacks cement.
Filled hole with heavy mud to 240 feet. Set second plug @ 240 feet w/20 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug @ 40 feet w/10 sacks cement.
Job complete @ 10:30 PM, April 4, 1970.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1970
CONSERVATION DIVISION
Wichita, Kansas

04-09-1970

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 7 day of April, 19 70

Feb. 1, 1972
Barbara J. Layton Notary Public.

15-135-20331-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MUSSELMAN #1
C NE/4 SW/4 Section 29-16S-22W
Ness County, Kansas

Commenced: March 24, 1970
Completed: April 4, 1970

OPERATOR - Nadel & Gussman

DEPTH		FORMATION	REMARKS
From	To		
0	259	Soil, Clay, Sand and Shale	Ran 8 joints 8-5/8" casing, set @ 257' w/165 sacks cement.
259	860	Shale	
860	980	Shale and Shells	
980	1050	Sand	
1050	1200	Shale and Shells	
1200	1520	Sand	
1520	1690	Shale and Shells	
1690	1760	Shale	
1760	1804	Anhydrite	
1804	2050	Shale and Shells	
2050	2440	Shale, Shells and Lime	
2440	3870	Shale and Lime	
3870	4075	Lime	
4075	4158	Lime and Shale	
4158	4445	Lime	
4445	4495	Lime and Shale	
4495	4535	Lime, Chert and Shale	
4535	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1970
CONSERVATION DIVISION
Wichita, Kansas
04-09-1970

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE/4 SW/4 Section 29-16S-22W, Ness County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 7 day of April, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

