

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-135-24224-0000

LEASE NAME W & K

WELL NUMBER 1

1,200 Ft. from S Section Line

1,320 Ft. from E Section Line

SEC. 19 TWP. 16 RGE. 22 (R) or (W)

COUNTY Ness

Date Well Completed 6-20-03

Plugging Commenced 6-20-03

Plugging Completed 6-20-03

RECEIVED  
06-25-2003  
JUN 25 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Coral Coast Petroleum, LC

ADDRESS 200 East First, STE #001, Wichita, KS

PHONE/(316) 269-1233 OPERATORS LICENSE NO. 31691

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-03 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? No if not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4,520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	227'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 1,800', pump 50 sax cement down drill pipe; push bridge plug to 1,050', pump 80 sax cement down drill pipe. push bridge plug to 260', pump 40 sax cement down drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coral Coast Petroleum, LC

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. Contractor (Employee of ~~Operator~~) or ~~Operator~~ above-described well, being first duly sworn on oath, says: That I have knowledge of the fact: statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 2003

My Commission Expires:



Ruth Phillips  
Notary Public



15-135-24224-00-00

Shields

WELL LOG

RECEIVED


06-25-2003  
JUN 25 2003

Russell, Kansas

KCC WICHITA

Operator: Coral Coast Petroleum, LC  
Well: W & K #1  
Commenced: June 10, 2003  
Completed: June 20, 2003  
Contractor: Shields Drilling Co.

Well Description: 120' South of Center of  
SE/4  
Sec. 19-16S-22W  
Ness County, KS



Elevation: 2,430' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	227'	Cmtd. w/160 sax

..... Figures Indicate Bottom of Formations .....

Sand & shale	1,766'	
Anhydrite	1,803'	
Shale	3,444'	
Shale & lime	4,200'	
Lime	4,368'	
Ft. Scott	4,377'	
Lime	4,445'	
Mississippi	4,520'	RTD

Notes