

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 190 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,682-00-00

LEASE NAME WEEKS

WELL NUMBER 1-33

1650 Ft. from (S) Section Line

1650 Ft. from (NW) Section Line

SEC. 33 TWP. 16 RGE. 22 (R) or (W)

COUNTY NESS

Date Well Completed 6-21-92

Plugging Commenced 6-21-92

Plugging Completed 6-21-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR BRITO OIL COMPANY, INC.

ADDRESS 200 E. First, Suite 208 Wichita, KS. 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 21, 1992 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? by oper. If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	232	8 5/8"	232	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug @ 1780' W/50 sx., 2nd plug @ 900' W/80 sx., 3rd plug @ 240' W/40 sx., 4th plug @ 40' W/10 sx., 15 sx. in rathole. Total 195 sx. 60/40 Pozmix, 6% Gel (1/4# flo-seal per sack @900'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~Agent~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Greg Davidson

(Address) R.R. 1 Box 183 Great Bend, KS.

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1992

Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

My Commission Expires: 5-20-93



DRILLER'S WELL LOG

0 - 232 Shales
 232 - 730 Shales & Sand
 730 - 3775 Lime & Shale
 3775 - 3955 Lime
 3955 - 4105 Lime & Shale
 4105 - 4235 Lime
 4235 - 4530 Lime & Shale
 4530 RTD

BRITO OIL COMPANY, INC.
 Weeks #1-33
 SW NE SW Sec. 33-16S-22W
 Ness County, Kansas

ELEVATION: 2431' GL 2436' KB

FORMATION DATA: (sample)

Anhy.	1740	(+696)
Base Anhy.	1775	(+661)
Heebner	3848	(-1412)
Lansing	3886	(-1450)
Muncie CReek	4019	(-1583)
Stark	4108	(-1672)
NLC	4156	(-1720)
Pawnee	4265	(-1829)
Ft. Scott	4360	(-1924)
Cher.Shale	4374	(-1938)
Base Cher. Lime	4442	(-2006)
Mississippian	4504	(-2068)
RTD	4530	(-2094)

SURFACE CASING:

8 5/8" set @ 232' W/140 sx. 60/40
Pozmix, 2% Gel, 3% CC

A F F I D A V I T


STATE OF KANSAS)
COUNTY OF BARTON) ^{ss}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson
RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 24th day of June, 1992

JUN 25 1992
06-25-1992
CONSERVATION DIVISION
Wichita, Kansas



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93