

State of Kansas



15-101-20079-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1974  
04-29-1974  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sonny Bigheart of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:Mr. Bigheart guarantees payment of the plugging fee.Operator's full Name: Abercrombie Drilling, Incorporated,Complete Address: 801 Union Center, Wichita, Kansas.Lease Name: Hineman Well No. 1Location: 150' E of CNE-SE Sec. 23 Twp. 19 Rge. (E)(W) 28County: Lane Total Depth 4400' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Bigheart was instructed to plug the well as follows:213'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 925'.Circulate hole with heavy mud. Pull DP to 1140' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,


  
 Conservation Division Agent