



15-135-20088-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

DEC 5 1967
12-05-1967
CONSERVATION DIVISION

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Nelson of Walters Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Walters Drlg. Co. & McClure Oil Co.

Complete Address: 400 Insurance Bldg., Wickita, Ks.

Lease Name: Schwartzkoph Well No. 1

Location: C NE NW Sec. 15 Twp. 16 Rge. 21 (E)(W)X

County: Ess Total Depth 4250 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Ken F. [Signature]
Conservation Division Agent