



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC 26 1967  
12-26-1967  
DIVISION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drlg. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg Co. Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name: Stephens Well No. 1

Location: C NW SW Sec. 27 Twp. 16 Rge. 21 (E)(W) X

County: Bess Total Depth 4235 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Burris was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
100 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent