

State of Kansas



15-135-30358-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

NOV 2 1967  
11-02-1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Oller of Murfin Drlg. Co. has this  
date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Zenith Drlg. Corp., Inc.

Complete Address: Suite 737 300 west Douglas Wichita, Kansas

Lease Name: Skaggs Well No. 1

Location: C NW SW Sec. 24 Twp. 16 Rge. 21 (E)(W) X

County Ness Total Depth 4155 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680' and displace  
100 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

L. F. Massey  
Conservation Division Agent