



15-135-20235-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1969
CONSERVATION DIVISION
Wichita, Kansas

04-23-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burriss of Chief Drlg. has this date requested permission to plug the following described well:

Mr. Burriss guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg. Co., Inc.

Complete Address: Box 797 Great Bend, Ks.

Lease Name: Irvin Well No. 1

Location: C SW SE Sec. 32 Twp. 16 Rge. 21 (E)(W) XX

County: Ness Total Depth 4289 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burriss was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680' and displace

50 sk cmt thru drill pipe. Heavy mud to 550' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Geo F. Wessley
Conservation Division Agent