

To: 1 020478  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-25 API NUMBER 15- 135-23,684-00-00 2025  
NE SE SW, SEC. 16, T. 16 S, R. 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name & Address: 125 N. Market, Suite 1000  
Wichita, KS 67202

990 feet from S section line  
2310 feet from W E section line  
Lease Name John Irvin Well # 1  
County Ness  
Well Total Depth 4325 140.56 feet  
Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_  
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8348

Company to plug at: Hour: 8 a.m. Day: 25 Month: 7 Year: 19 92

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1649-87'

1st plug at 1680' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,  
3rd plug at 240' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1680' with 50 sx cement,  
2nd plug at 1000' with 80 sx cement,  
3rd plug at 240' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

I hereby certify that I have observed this plugging.

INVOICED  
DATE 8-4-92  
INV. NO. 3585

RECEIVED  
STATE CORPORATION COMMISSION  
07-29-1992  
JUL 29 1992  
SIGNED Glenn R. Goodrow  
(TECHNICIAN)  
CONSERVATION DIVISION  
WICHITA, KANSAS

EFFECTIVE DATE: 10-10-92  
DISTRICT # 1  
SSA? Yes No

State of Kansas  
NOTICE OF INTENTION TO DRILL

15-135-23,684-00-00

FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .....  
month day year

Spot  
 NE  SE  SW Sec 16 Twp 16 S. Rg 21W East  
West

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: 125 N. Market, Suite 1000  
City/State/Zip: Wichita, KS 67202  
Contact Person: Bob Mathiesen  
Phone: (316) 267-4375

990 ..... feet from South North line of Section  
 2310 ..... feet from East / West line of Section  
IS SECTION X REGULAR \_\_\_\_\_ IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Ness  
Lease Name: John Irvin Well #: 1  
Field Name: wildcat

CONTRACTOR: License #: Whit & Ellis  
Name: unknown

Is this a Prorated/Spaced Field? .... yes X no  
Target Formation(s): Cherokee  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2350' est ..... feet MSL  
Water well within one-quarter mile: X yes .... no  
Public water supply well within one mile: .... yes X no  
Depth to bottom of fresh water: 120'  
Depth to bottom of usable water: 1000'  
Surface Pipe by Alternate: .... 1 X 2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: none  
Projected Total Depth: 4350'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
..... well .... farm pond X other

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWD ... Disposal  Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
... Other .....

If OWD: old well information as follows:  
Operator: .....  
Well Name: .....  
Comp. Date: ..... Old Total Depth .....

Directional, Deviated or Horizontal wellbore? .... yes X no  
If yes, true vertical depth: .....  
Bottom Hole Location: .....

AFFIDAVIT

200' Alt. II Req.

Exp. 12/5/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Judy

SPUD DATE 7-17-92 INIT. Sm

LENGTH SURFACE PLANNED 200'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/2" @ 270 CONDUCTOR  
ANHYDRITE T- 1649 B- 1657 ELEVATION

TD 4325 FORMATION Miss

RAN PIPE @ SX DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @        Ft. W/ SX

Hug./Council @        Ft. W/ SX

1687 Anhydrite Base @ 1680 Ft. W/ 50 SX

       1/2 Base Anyh. @ 950 Ft. W/ 80 SX

       1/2, 1/2 Plug @ 445 Ft. W/ 50 SX

       Bottom Surface @ 240 Ft. W/ 50 SX

       40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/        SX

WATER WELL NO SX (Irr. Well        Pond       )  
Hauling X

TECHNICIAN GB DATE 7-21-92

TYPE OF CEMENT: 60/40 Pas

STARTING TIME 8:00 (AM/PM) DATE 7-25-92

COMPLETION TIME 11:30 (AM/PM) DATE 7-25-92

CEMENT Allied

Andrew gave final plug orders

RECEIVED  
WICHITA COUNTY COMMISSION  
DATE 9-9-92  
Wichita Kansas