

To: 120744
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-23

API NUMBER 15- 101-21,635-00-00 140
NE NE NE, SEC. 35, T. 19 S, R. 28

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Ste. 1000
Wichita, KS 67202

4950 feet from S section line
330 feet from E section line

Lease Name Shaffer-35A Well # 1
County Lane Lane 150.87

Well Total Depth 4642 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 214

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 9:30 p.m. Day: 22 Month: 10 Year: 19 92

Plugging proposal received from Robert Kasper

(company name) White & Ellis Drilling (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2043-72'

1st plug at 2070' with 50 sx cement, 2nd plug at 1100' with 50 sx cement,

3rd plug at 550' with 50 sx cement, 4th plug at 240' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12 a.m. Day: 23 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,

2nd plug at 1100' with 50 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 240' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-16-92

DATE 11-16-92

INV. NO. 36760

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
10-26-1992
OCT 26 1992
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 10-13-92

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1
SEAT Yes No

NOTICE OF INTENTION TO DRILL 101-21,635-0000

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 15 92
month day year

Spot NE NE NE Sec 35 Twp 19 S. Rg 28W East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: (316) 267-4375

4950 feet from South / North line of Section
330 feet from East / West line of Section
IS SECTION REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Laba
Lease Name: Shaffer-35A Well #: 1
Field Name: Hackberry Creek South

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling Co.

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): L/KC

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2719' est. feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 75'
Depth to bottom of usable water: 1175'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'

Length of Conductor pipe required: none
Projected Total Depth: 4650'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

well farm pond X other
DWR Permit #:

Will Cores Be Taken?: yes X no
If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWWD Disposal Wildcat Cable
Seismic # of Holes Other
If OWWD, old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

200' Alt. II Req.

Exp. 4/8/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met.

Pusher Robert Casper
SPUD DATE 10-15-92 INIT. DG
LENGTH SURFACE PLANNED 200'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8" @ 215' CONDUCTOR
ANHYDRITE T-20-13 B-72- ELEVATION
TD 4642' FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2070 Ft. W/ 50 SX
1/2 Base Anyh. @ 1600 Ft. W/ 50 SX
1/2, 1/2 Plug @ 500 Ft. W/ 50 SX
Bottom Surface @ 240 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 16 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN DR DATE 10-21-92
TYPE OF CEMENT 60-40-670 4.75.
START TIME 6:30 (AM/PM) DATE 10-23-92
COMPLETION TIME 2:00 (AM/PM) DATE 10-23-92
CEMENT COMPANY Allied
RECEIVED 10-26-92
Wichita, Kansas CONSERVATION DIVISION
STATE OF KANSAS COMMISSION 1992