

1 051584

10-10

STATE CORPORATION COMMISSION
OBSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767Operator: Ritchie Exploration, Inc.Name: 125 N. Market, Ste. 1000Address: Wichita, KS 67202

API NUMBER 15-101-21,633-00-00 84R
30' S of
SE NW NW, SEC. 30, T. 19 S, R 28 W/EX

1020 feet from NX section line990 feet from WE section lineLease Name Luella Speer Well # 1County Lane 151.87Well Total Depth 4673 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 207Abandoned Oil Well Gas Well Input Well SMD Well O&A xOther well as hereinafter indicated Plugging Contractor White & Ellis Drilling Company License Number 5420Address P.O. Box 48848, Wichita, KS 67201-8848Company to plug at: Hour: 10 p.m. Day: 10 Month: 10 Year: 19 92Plugging proposal received from Judy(company name) White & Ellis Drilling Company (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2155-83'

1st plug at 2180' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None xOperations Completed: Hour: 12:30 p.m. Day: 10 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,

2nd plug at 1250' with 80 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.(If additional description is necessary, use BACK of this form.)
XXXX (did not) observe this plugging.DATE 10-29-92 Signed Richard W. Lacey
36643 (TECHNICIAN)

DISTRICT: 10
Must be approved by the K.C.C. five (5) days prior to commencing well
Expected Spud Date: 9 month 15 day 92 year
OPERATOR: License #: 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: (316) 267-4375

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling Co.

Well Drilled For: Well Class: Type Equipment:
Oil ☒ Enh Rec ☐ Infield ☒ Mud Rotary
Gas ☐ Storage ☐ Pool Ext. ☐ Air Rotary
CWD ☐ Disposal ☒ Wildcat ☐ Cable
Seismic: ☐ # of Holes ☐ Other
Other
If CWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ☒ yes ☐ no
If yes, true vertical depth:
Bottom Hole Location:

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

SE 30 15 6 NW 30 19 S. Rg 28W East
1020 feet from South / North line of Section
990 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: Luella Spaer Well #: 1
Field Name: Wildcat
Is this a Prorated/Spaced Field? ☒ yes ☐ no
Target Formation(s): L/KC
Nearest lease or unit boundary: 990
Ground Surface Elevation: 2808 est. feet NSL
Water well within one-quarter mile: ☐ yes ☒ no
Public water supply well within one mile: ☐ yes ☒ no
Depth to bottom of fresh water: 90
Depth to bottom of usable water: 1220
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200
Length of Conductor pipe required: none
Projected Total Depth: 4700
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond ☒ other
DWR Permit #:
Will Cores Be Taken?: ☒ yes ☐ no
If yes, proposed zone: 200' Alt II Reg

Pusher: John
SPUD DATE: 10-2-92 INIT. SM
LENGTH SURFACE PLANNED: 200 +
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4 @ 207 CONDUCTOR
ANHYDRITE T-2155 B-2183 ELEVATION
TD 4673 FORMATION Miss
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2180 Ft. W/ 50 SX
1/2 Base Anyh. @ 1250 Ft. W/ 80 SX
1/2, 1/2 Plug @ 600 Ft. W/ 40 SX
Bottom Surface @ 230 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN R.L. DATE 10-5-92
TYPE OF CEMENT 60/40 per 6% grt 1/4 Flow sm
STARTING TIME 10:00 (AM/PM) DATE 10-10-92
COMPLETION TIME 12:30 (AM/PM) DATE 10-10-92
CEMENT COMPANY 51002
10-15-1992