

1 030445

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,182-0000

NW SE NE, SEC. 29, T 19 S, R 28 W/X

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Hineman "A" Well # 1

Operator: Chief Drilling Co., Inc.

County Lane 154.05

Name & Address 905 Century Plaza

Well Total Depth 4740 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 20 Month: June Year: 19 85

Plugging proposal received from Harold Dinkle

(company name) Warrior (phone) 913-726-4875

Elevation 2788'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2136-2170'

1st plug at 2190' with 50 sx cement

2nd plug at 1100' with 70 sx cement

3rd plug at 360' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30 am Day: 21 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1100' with 70

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge -- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
07-01-1985
JUL 01 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of THIS form.)

(operator did not) observe this plugging.

INVOICED
DATE 7-10-85
8793
INV. NO.

Signed Steve Durrant
(TECHNICIAN)