

1 110360

6-16-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 N/2 NW, SEC. 29, T 19 S, R 28 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,394-00-00
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

3960 feet from E section line
Lease Name Toburen B Well # 1

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

County Lane 153.24
Well Total Depth 4715 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Bldg., 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 15 Month: 6 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2150' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 340' with 40 sx cement

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 a.m. Day: 16 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1987
06-19-1987
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-22-87
INV. NO. 17296 6-16

Signed James Kapp (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date June 8 1987 month day year

API Number 15- 101-21,394-0000
N/2 N/2 NW/4 Sec. 29 Twp. 19 S, Rg. 28 X West
4950' Ft. from South Line of Section
3960' Ft. from East Line of Section

OPERATOR: License # 5181
Name SLAWSON, DONALD C.
Address 200 Douglas Building
City/State/Zip Wichita, Kansas 67202
Contact Person Bill Horigan
Phone (316) 263-3201

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330' feet
County Lane
Lease Name TOBUREN 'B' Well # 1

CONTRACTOR: License # 5657
Name Slawson Drlg. Co.
City/State Wichita, Kansas

Ground surface elevation 2792' GR. (SATA) feet MSL
Domestic well within 550 feet yes no
Municipal well within one mile yes no

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Depth to bottom of fresh water 190'
Depth to bottom of usable water 2250' / 1.25
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 320'
Conductor pipe required
Projected Total Depth 4650' feet
Formation Mississippian

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Western Kansas
Date 6/4/87 Signature of Operator or Agent Title Geologist

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt.
This Authorization Expires 12-9-87 Approved By 6-4-87

6-887
316-3201

no WW
[Signature]

N/2 N/2 NW/4 Sec. 29 Twp. 19 S, Rg. 28 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 2225' or formation with 50sx feet of 60/40 Poz. w/6% Gel
2nd plug @ ft. deep 1350' or formation with 60sx feet of 60/40 Poz. w/6% Gel
3rd plug @ ft. deep 350' or formation with 40sx feet of 60/40 Poz. w/6% Gel
4th plug @ ft. deep 40' or formation with 10sx feet of 60/40 Poz. w/6% Gel
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet 10sx (b) Mousehole to surface minus 5 feet

Plugged

PUSHER Bot Ravel
TD 47' 5" FORMATION Main
SURFACE PIPE 320' @ 2 1/2"
ANHYDRITE ELEVATION
STARTING TIME & DATE 11:00 PM
COMPLETION TIME & DATE AM 6-16-87
1st PLUG @ 2150 FT. W/ 50 SX
2nd PLUG @ 1350 FT. W/ 80 SX
3rd PLUG @ 340 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY All
TECHNICIAN James R. [Signature]

STATE OF KANSAS
JUN 19 1987
06-19-1987
WICHITA, KANSAS

60/40/690 alcd