

2-7-88

To: 1 051008
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,452-00-00

SW SW NE, SEC. 28, T 19 S, R 28 W/R

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name James Well # 1

Operator: Palomino Petroleum

County Lane 153.56

Name: Route 5, Box 51-C

Well Total Depth 4725 feet

Address: Newton, KS 67114

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling Company, Inc. License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 1 p.m. Day: 7 Month: 2 Year: 19 88

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling Company, Inc. (phone) 913-628-2296

Elevation 2780'

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2120-50'

1st plug at 2150' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 230' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 p.m. Day: 7 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 230' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

DATE 2-12-88

WV. NO. 19833

2-7

Signed Richard M. Lacey
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 1 19 88
month day yearAPI Number 15- 101-21,452-00-00
SW SW NE Sec. 28 Twp. 19 S, Rg. 28 X East
2970 Ft. from South Line of Section
2310 Ft. from East Line of SectionOPERATOR: License # 5161
Name Palomino Petroleum
Address Route 5 Box 51-C
City/State/Zip Newton, KS 67114
Contact Person Bob Watchous
Phone (316) 283-0232(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County LaneCONTRACTOR: License # 4083
Name Western Kansas Drilling Co., Inc.
City/State Hays, KS 67601Lease Name James Well # 1
Ground surface elevation 2780 est. feet MSLWell Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext. Air Rotary
OWWO Expl X Wildcat CableDomestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Operator Bob Watchous
Well Name James
Comp Date 1-5-88 Old Total Depth 4700Depth to bottom of fresh water. 80
Depth to bottom of usable water 1050 1250

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.

Date 1-5-88 Signature of Operator or Agent Bob Watchous Title Owner

For KCC Use:

Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 7-6-88 Approved By PCH 1-6-88EFFECTIVE DATE: 1-11-88Move in 1-29-87 at 2004SW SW NE Sec. 28 Twp. 19 S, Rg. 28 X East
West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep.....	2140	or formation with.....	50 sacks	feet of.....	cement
2nd plug @ ft. deep.....	1400	or formation with.....	50 sacks	feet of.....	cement
3rd plug @ ft. deep.....	350	or formation with.....	50 sacks	feet of.....	cement
4th plug @ ft. deep.....	40-0	or formation with.....	10 sacks	feet of.....	cement
5th plug @ ft. deep.....		or formation with.....		feet of.....	
(a) Rathole to surface minus 5 feet	15 sacks				
				(b) Mousehole to surface minus 5 feet	10 sacks

PUSHER

TD

SURFACE PIPE

ANHYDRITE

STARTING TIME & DATE

COMPLETION TIME & DATE

1st PLUG @

2nd PLUG @

3rd PLUG @

4th PLUG @

RAT HOLE CIRCULATED W/

MOUSE HOLE CIRCULATED W/

WATER WELL PLUGGED W/

CEMENT COMPANY

TECHNICIAN

STATE OF KANSAS

FEB 10 1988

CONFIRMED

02-10-1988