

1 030297

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,053-00-00

SW NW NW, SEC. 28, T. 19 S, R. 28 W
4290 feet N SE Corner of ~~XXX~~ section line
4950 feet W SE Corner of ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Speer Well # 1

Operator: Palomino Petroleum

County _____ Lane _____

Name & _____

Address P. O. Box 18610

Well Total Depth 4700 152.75 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Strata Drilling Co. License Number 6188

Address Box 355, Great Bend, KS 67530

Company to plug at: Hour: 1:00 pm Day: 3 Month: October Year: 19 84

Plugging proposal received from Howard Cain

(company name) Strata (phone) 316-793-7971

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2130' with 50 sx cement

2nd plug at 1050' with 50 sx cement

3rd plug at 660' with 50 sx cement

4th plug at 330' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Steve Dumont
Cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 10 sx

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:45 pm Day: 3 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement, 2nd plug at 1050' with 50

sx cement, 3rd plug at 660' with 50 sx cement, 4th plug at 330' with 40 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-15-84

Signed Steve Dumont
(TECHNICIAN)

INV. NO. 4317

RECEIVED
STATE CORPORATION COMMISSION
OCT 09 1984
10-09-1984
CONSERVATION DIVISION
Wichita, Ks