

To: 1 040347 4-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,615-00-00
110' N of
SE SE SE, SEC. 26, T. 19 S, R. 28 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market, Suite 1000
Wichita, KS 67202

440 feet from S section line
330 feet from E section line
Lease Name Gerald Riley Well # 2
County Lane
Well Total Depth 4650 151.12 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 6:30 a.m. Day: 16 Month: 4 Year: 19 92
Plugging proposal received from Judy

(company name) White & Ellis Drilling Company (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2056-88'
1st plug at 2090' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 240' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 11:45 a.m. Day: 16 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2090' with 50 sx cement,
2nd plug at 1200' with 80 sx cement,
3rd plug at 600' with 50 sx cement,
4th plug at 240' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 20 1992
04-20-1992
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If you did not observe this plugging.)

DATE 5-5-92
INV. NO. 3515

Signed Stephen J. Pfeifer
(TECHNICIAN)

EFFECTIVE DATE: 2-18-92
DISTRICT #
SSA Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 101-21,615-00-00
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 1 1992
month day year

APP Spot 110' N OF
SE SE SE Sec 26 Twp 19 S Rg 20 East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, #1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: (316) 267-4275

440' feet from South / North line of Section
330' feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Lane
Lease Name: Gerald Riley Well #: 2
Field Name: Hackberry Creek South

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Lansing-KC

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2741 est. feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 75'
Depth to bottom of usable water: 1175'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 250'

Length of Conductor pipe required: none
Projected Total Depth: 4650'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

well farm pond X other

DWR Permit #:
Will Cores Be Taken?: yes X no

If yes, proposed zone:

260- Dennis Anderson
Alt: II Req. 4-17-92

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
Gas ... Storage X Pool Ext. ... Air Rotary
OAWD ... Disposal ... Wildcat ... Cable
Seismic: # of Holes Other

If OAWD: old well information as follows:
Operator:
Well Name:
Comp. Date:

Directional, Deviated or Horizontal well? X no
If yes, true vertical depth:

Bottom Hole Location: APR 20 1992
Exp. 8/13/92

RECEIVED
KANSAS CORPORATION COMMISSION
APR 20 1992
04-20-1992
AFFIDAVIT
CONSERVATION DIVISION
WICHITA, KS

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Judy
SPUD DATE 4-7 or 8-92 INIT. DR
LENGTH SURFACE PLANNED 250
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/4 @ 3.10' CONDUCTOR
ANHYDRITE T-2056 B-2084 ELEVATION
TD 4650 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2090' Ft. W/ 50 SX
1/2 Base Anhy. @ 1200' Ft. W/ 80 SX
1/2, 1/2 Plug @ 600' Ft. W/ 50 SX
Bottom Surface @ 240' Ft. W/ 40 SX
40' Plug @ 40' Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN S.P. DATE 4-9-92
TYPE OF CEMENT 60/80 ps. 6 gal. 4 1/4 lbs. Seal
STARTING TIME 6:30 (AM/PM) DATE 4-16-92
COMPLETION TIME 11:45 (AM/PM) DATE
CEMENT COMPANY Allied