

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21486-00-00
Spot: CNWSWNW Sec/Twnshp/Rge: 26-19S-28W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: MOWERY Well Number: 1
County: LANE Total Vertical Depth: 4690 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 7802
WICHITA, KS 67278

Production Casing Size: 4.5 feet: 4426 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 306 WITH 150 SX CMT
\$152.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2003 9:20 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DARYL HANSON Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS FOR BOTTOM PLUG. PUMP 13 SX GEL & 120 SX. PRESSURE TEST. TIE ONTO BACKSIE & PUMP 15 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/11/2003 10:40 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4417'. PERFS AT 4345-4348'. WELL HAS BEEN 2-STAGED. CMT FROM 2010' TO SURFACE WITH 250 SX CMT. PUMP 20 SX CMT & 200# HULLS FOR BOTTOM PLUG. PUMP 13 SX GEL & 120 SX CMT. MAXIMUM PRESSURE 1400#. SHUT IN PRESSURE 800#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED
FEB 27 2003
KCC WICHITA
02-27-03

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED
DATE 2-27-03
INV. NO. 2003061239

FORK CSG