

3-23

229 K

Job: 1 020364
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION of W/2 SE SE, SEC. 26, T 19 S, R 28 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,571-00-00
50' S & 30' E
610 feet from S section line
960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

Lease Name Gerald Riley Well # 1
County Lane Lane 151.12
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 23 Month: 3 Year: 19 91

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling Company (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2663-2091'
1st plug at 2091' with 50 sx cement, 2nd plug at 1150' with 50 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 240' with 40 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 a.m. Day: 23 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2091' with 50 sx cement,

2nd plug at 1150' with 50 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-9-91
INV. NO. 31429

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
03-26-1991
MAR 26 1991
CONSERVATION DIVISION
WICHITA, KANSAS

EFFECTIVE DATE: 2-10-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

101-21,571 - 00-00

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 2 10 91
month day year

W/2 SE SE Sec 26 Twp 19 S, Rg 28 X East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: 316/267-4375

660 610 feet from South line of Section
660 760 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling Co.

County: Lane
Lease Name: Gerald Riley Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes X no
Target Formation(s): Lansing-Kansas City
Nearest lease or unit boundary: 660
Ground Surface Elevation: 2745 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 75
Depth to bottom of usable water: 1175
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200
Length of Conductor pipe required: NONE
Projected Total Depth: 4650
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond ... X other
DWR Permit #: _____
Will Cores Be Taken?: yes X no
If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... X Wildcat ... Cable
... Seismic; ... # of Holes

RECEIVED
STATE CORPORATION COMMISSION
03-26-1991
MAR 26 1991
CONSERVATION DIVISION
Wichita, Kansas

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth: _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: _____

Exp. 8/5/91

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Bob Casper
SPUD DATE 3-13-91 INIT. 05
LENGTH SURFACE PLANNED 200'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. _____ bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 2 1/2 @ 210 CONDUCTOR _____
ANHYDRITE T- 2663 B- 2091 ELEVATION _____
TD 4650 FORMATION Miss
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
_____ Arbuckle Plug @ _____ Ft. W/ SX
_____ Hug./Council @ _____ Ft. W/ SX
_____ Anhydrite Base @ 2091 Ft. W/ 50 SX
_____ 1/2 Base Anyh. @ 1150 Ft. W/ 50 SX
_____ 1/2, 1/2 Plug @ 1000 Ft. W/ 50 SX
_____ Bottom Surface @ 240 Ft. W/ 40 SX
_____ 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL _____ SX (Irr. Well) Pond _____
TECHNICIAN GB DATE _____ Hauling _____
TYPE OF CEMENT 60/40 pos 690
STARTING TIME 4:00 (AM/PM) DATE 3-21-91
COMPLETION TIME 6:45 (AM/PM) DATE 3-21-91
CEMENT COMPANY Allied