

7-23

1 070830

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
260 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,342-00-00  
C NE NE, SEC. 15, T 16 S, R 21 W/E  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Cline Well # 1

Operator: BEREXCO

County Ness 137.80

Name & Address 970 Fourth Financial Center  
Wichita, KS 67202

Well Total Depth 4240 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BEREXCO License Number 5363

Address 970 Fourth Financial Center, Wichita, KS 67202

Company to plug at: Hour: 2:30 p.m. Day: 23 Month: 7 Year: 19 90

Plugging proposal received from George Jorgensen

(company name) BEREXCO (phone) 316-265-3311

were: 4 1/2" at 4240' w/100 sx cement, PBDT 4175', Perfs at 4123-35'

1st plug set CIBP at 4000' with 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4000' with 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

and 175 sx cement down 8 5/8".

Maximum pressure 800 psi and shut in 500 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
07-25-1990  
JUL 25 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2349' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-30-90

INV. NO. 28809

Signed Dan Jordan  
(TECHNICIAN)