

12-17-87

1030895

API NUMBER 15-135-23,187-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NE, SEC. 14, T 16 S, R 21 WAK
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Ryan Well # 1

Operator: Thornton E. Anderson
Name & Address: 212 North Market, Suite 508
Wichita, KS 67202

County Ness 138.13
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 17 Month: 12 Year: 19 87

Plugging proposal received from Walt Oden

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1552-91'
1st plug at 1560' with 50 sx cement, 2nd plug at 780' with 75 sx cement,
3rd plug at 270' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 p.m. Day: 17 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,
2nd plug at 780' with 75 sx cement,
3rd plug at 270' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

12-22-1987
RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
Should observe this plugging.

Signed Steve Durrant MS (TECHNICIAN)

DATE 1-6-88

INV. NO. 19350

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

(see rules on reverse side)

Expected Spud Date... November 15, 1987
month day year

API Number 15- 135-23,187-0000

OPERATOR: License # 6484
Name Thornton E. Anderson
Address 212 N. Market, Suite 508
City/State/Zip Wichita, KS 67202
Contact Person William L. Anderson
Phone 265-7929

NW SW NE Sec 14 Twp 16 S. Rg. 21
3630 Ft. from South Line of Section
2310 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Ness

CONTRACTOR: License # 5302
Name Red Tiger Drilling Company
City/State Wichita, KS 67202

Lease Name Ryan Well # 1
Ground surface elevation 2262 feet MSL
Domestic well within 330 feet yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Municipal well within one mile yes no
Depth to bottom of fresh water 500 feet
Depth to bottom of usable water 650 feet
Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set 250 feet

If OWWO: old well info as follows:
Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____

Conductor pipe required NA
Projected Total Depth 4250 feet
Formation Mississippi

I certify that well will comply with K.S.A. 85-101, et seq. plus eventually plugging hole to KCC specifications.
Date 10/27/87 Signature of Operator or Agent William L. Anderson, Operations Manager

For KCC Use:
Conductor Pipe Required _____ feet; Minimum Surface Pipe Required 200 feet per Alt. Y0
This Authorization Expires 5-25-88 Approved By PH 11-5-87 No Use

EFFECTIVE DATE 11-10-87

Move in 12-22-87 7:00 PM @ 230

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	Anhydrite	or formation with	100	feet of	CEMENT
2nd plug @ ft. deep	Base of s/c pipe	or formation with	10	feet of	CEMENT
3rd plug @ ft. deep	SURFACE	or formation with	10	feet of	CEMENT
4th plug @ ft. deep		or formation with		feet of	
5th plug @ ft. deep		or formation with		feet of	

(a) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Mc Craken #14 N
Web 3 - 1/2 D -

PUSHER Walt Odene

TD 4250 FORMATION MISS

SURFACE PIPE 8 5/8 @ 251

ANHYDRITE 1557 ELEVATION 2262GL

STARTING TIME & DATE 11:30 AM 12-17-87

COMPLETION TIME & DATE 3:30 PM

1st PLUG @ 1560 FT. W/ 50 SX

2nd PLUG @ 780 FT. W/ 75 SX

3rd PLUG @ 270 FT. W/ 40 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ — SX

WATER WELL PLUGGED W/ ALLIED SX

CEMENT COMPANY 614 696901

TECHNICIAN SR

12-22-1987
REC'D 12-22-1987
Wichita, Kansas
DIVISION